


HOLLOW DRIG.CO., INC. ET AL
A.E. Harrel No. 2.

SEC. 36 T. 26 R. 13 W
SW NE NE

Total Depth. 4329'

County. Pratt

Comm. 3-31-43 Comp. 5-8-43
Shot or Treated. 5-8-43 1000 Gals. Acid
Contractor. Jock Garden Cont. Co.
Issued. 7-17-43



CASING:
8 5/8" 477' Cem.
5 1/2" 4314' Cem.

Elevation.

Production. Ind. Cap. 6810 B.
Deptho. Pot.

Figures Indicate Bottom of Formations.

sand	270
red bed	477
red bed & shale	850
shale red	975
shale & shells	1680
shale	1725
lime & shale	1865
lime brkn	1950
shale & lime	2000
lime brkn & shale	2080
shale	2115
shale & shells	2330
lime & shale	2390
shale	2485
lime brkn	2515
shale	2660
shale & shells	2725
lime brkn & shale	2760
shale & shells	2895
shale & lime	2945
shale	3180
lime	3310
lime brkn	3410
lime	3570
lime & shale	3635
lime	4050
lime & shale	4080
shale & chert	4095
lime & chert	4140
shale & chert	4180
lime & chert	4205
shale & sand	4220
shale	4306
lime	4314

T. D. rotary
lime Arbuckle 4324
dolomite, 2400' Oil
11 hrs 4326
dolomite 4329
Total Depth.

Tops:
Ft. Riley 2083
Florence Flint 2218
Base Fl. Flint 2238
Topeka 3165
Heebner 3525
Base Oread 3560
"Brown" Lime 3694
Lansing 3715
Mississippian 4119
Kinderhook 4140
Viola 4154
Simpson 4190
Arbuckle 4305