


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- THE TEXAS CO.
Farm- Fred Smith No. 3

SEC. 6 T. 26 R. 13W
NE SW SE

Total Depth. 4050' PB 4014'
Comm. 2-8-55 Comp. 3-5-55
Shot or Treated.
Contractor. Noble Drlg. Co.
Issued. 4-30-55

County Pratt KANSAS



CASING:

10 3/4" 516' cem
7" 4049' cem w/225 sx

Elevation. 1962' DE

Production. Pmp. 184 BO, NW in
24 hrs.

Figures indicate Bottom of Formations.

surface sand	190
red beds	235
red beds & pea gravel	280
red beds & sand	513
Not shown	536
red beds	870
anhydrite	910
red beds & sand strks	1425
shale & sand	1775
lime	2140
lime w/shale strks	2515
lime & shale	2875
shale & lime	3015
lime & shale	3140
not shown	3218
shale w/lime strks	3275
lime w/shale strks	3365
lime & shale	3674
shale & lime	3765
lime & shale	3890
lime	3920
lime & shale	3994
lime	4050
Total Depth PB 4014'	

Tops:

Cimarron Dolomite	864
Heebner	3584
Brown Lansing	3743
Lansing	3767

Run 17 jts of 10 3/4" Csg, cemented with
300 sx at 7:30 P M 2-9-55
Recemented with 100 sx & 65 sx on 2-10-55
Recemented with 50 sx at 2:15 P M 2-14-55
Recemented with 15 sx & 100 sx on 2-20-55