


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
505 East Murdock, Wichita, Kansas

Company- BRUNSON-SPINES, INC.
Farm- Tremain No. 1

SEC. 14 T. 26 R. 13W
NE NE SW

Total Depth. 4360'
Comm. 1-22-59 Comp. 2-2-59
Shot or Treated.
Contractor. Brunson-Spines, Inc.
Issued. 6-20-59

County Pratt
KANSAS



Elevation. 1920' KB

Production. Dry

CASING:

12 1/4" 260'
3 5/8" 792'

Figures Indicate Bottom of Formations.

sand & clay	130
sandy shale	190
red bed & shale	345
red bed w/sand	787
Anhydrite	802
red bed, shale w/shells	1110
shale	1795
shale w/strks lime	1845
lime	1985
lime w/shale strks	2075
lime	2235
lime & shale	2760
shale w/lime strks	2925
sandy lime	2955
lime & shale	3385
sandy lime & shale	3540
lime & shale	3709
lime	3849
lime w/strks chert	3920
lime	4168
lime w/chert	4222
lime, shale & chert	4253
lime w/chert	4307
lime	4345
shale, sand & lime	4360
Total Depth	

TOPS:

Anhydrite (scout)	787
Heebner Shale	3558
Toronto	3580
Douglas Shale	3610
Brown Lime	3728
Lansing-Kansas City	3746
Base Kansas City	4065
Mississippi	4187
Simpson Shale	4319
Simpson Sand	4333