

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


Company- DAVIS BROTHERS
 Farm- Bales "A" No. 1

SEC. 18 T. 26 R. 13W
 NE SW NW

Total Depth. 4533'
 Comm. 4-1-59 Comp. 4-15-59
 Shot or Treated.
 Contractor. Prime Drilg. Co.
 Issued. 6-27-59

County Pratt

KANSAS



Elevation. 1970' KB

Production. Dry

CASING:

8 5/8" 346' cem w/275 sx.

Figures Indicate Bottom of Formations.

sand	180
sand & shale	225
shale & red bed	347
red bed & shale	860
Anhydrite	877
shale & red bed	1210
shale & shells	1305
shale & shells(lime strks)	1642
shale & lime streaks	1952
lime & shale	2525
shale & lime	2560
lime & shale	2690
shale & lime	2970
lime & shale	3405
lime	3608
shale & lime	3770
lime & shale	3875
lime	4105
lime & shale	4245
lime	4267
shale	4269
shale & sand	4300
lime	4365
cherty lime	4400
chert lime & sand	4437
shale, lime & sand	4490
lime & dolomite chert	4523 RTD
Total Depth	

TOPS:

Anhydrite (scout)	860
Heebner	3620
Brown Lime	3779
Lansing	3798
Base Kansas City	4095
Mississippi	4226
Kinderhook Sand	4279
Kinderhook Shale	4290
Viola	4302
Simpson Shale	4408
Simpson Sand	4435
Arbuckle	4494

Ran Schlumberger Laterolog Survey.

DST #1 3939-80', op 1 hr, gas to surf.
 in 46 mins., rec. 155' GCM & 73' slightly
 oil specked mud. 20" IBHSIP 1460#,
 30" FBHSIP 1210#, FP 40#-100#.

DST #2 3990-4105', op 45 min., rec. 41'
 mud, 20" IBHSIP 1280#, 30" FBHSIP 860#,
 FP 0#-0#.

DST #3 4274-4300', op 1 hr., rec. 13'
 mud, 20" IBHSIP C#, 30" FBHSIP C#,
 FP 0#-0#.