

HOENER

1

2

H. L. MOORE

WEST KANSAS

LEASE

WELL NO.

TEST NO.

COMPANY

DISTRICT


LOCATION	26-26S-13W				Date	6-12-53			
FIELD	Wildcat				Ticket No.	78213T			
COUNTY	Pratt				HOWCO DISTRICT	Pratt			
STATE	Kansas		HOLE & TOOL DATA		Kind of Job	Open Hole			
CONTRACTOR	Reserve Drllg. Co.		Total Depth	3971'	Casing Perforations	Top - Bottom -			
			Top Packer Depth	3943'	Bottom Packer Depth	-			
MUD DATA			Casing or Hole Size	7 7/8"	Liner or Rathole Size	-			
Kind	Starch		Formation Tested	Kansas City Lime		Extra Folder Charge	-		
Weight	9.9	lbs.-gal.	Size Drill Pipe	4 1/2" API FH	Size Drill Collars	6" x 83.57'	Jars	-	
Viscosity	39	Sec.	Size Bottom Choke	3/4"	Size Surface Choke	1 1/2"			
Filter Loss	10.5	c. c. Filter Cake	2/32	in.	Size Tool Valve	3/4"	Size Pilot Valve	-	
BT. P.R.D. No.	375	Blanked Off	No	Size Hook Wall Packer	-	Size Rings	-	No. Rings	-
12	Hr. Clock No.	2486	Size D. E Wall Packer	6 3/4"	No. Packers	1	Total	\$215.00	
Est. Gauge Depth Temp.	110	°F	PRD Device No.	1816	Blanked Off	Yes	Witnessed By	Wendell Johns	
Pressure Readings	Field	Office Corrected	Size & Length Anchor	4 1/2" x 28'	Tester				
Initial Hydro Mud Pressure		2054	p.s.i.	REMARKS: Opened tool with strong blow that diminished to					
Initial Flow Pres.		17	p.s.i.	weak blow and continued throughout test.					
Tool Open	60 minutes								
Final Flow Pres.		31	p.s.i.	Recovered 340' of gas, 80' slight oil and gas cut mud.					
Time Closed In	20 minutes								
Closed In Pres.		132	p.s.i.						
Final Hydro Mud Pressure		2054	p.s.i.	Amount of Cushion	None	All depths measured from	Kelly Bushing	No. Folders Reproduced	Five

TIME

PRESSURE


78213

Each Horizontal Line Equal to 1000 p.s.i.



WELL TIEBACK 00201

8





Telephone 7903


GREAT BEND, KANSAS TEST #1

TKT. #1645

TYPE C-D RECORDER

COMPANY H. L. MOORE WELL HOENER #1
DEPTH 3802' BOTTOM HOLE MUD PRESSURE 2070 #
CHOKES - TOP 1 1/2" BOTTOM 3/4" IF 140 #
SURFACE PRESSURE 0 BOTTOM PRESSURE FF 300 # SHUT-IN 1335 #
TESTED FROM 3786' TO 3802' DATE 6-9-53
RECOVERY.

60 FT. OF SLIGHTLY OIL & GAS CUT MUD
480 FT. OF GAS IN DRILL PIPE



H. L. MOORE COMPANY		KANSAS DISTRICT		
1 LEASE		3 TEST NO.		
1 WELL NO.				
LOCATION	Natrona		Date	6-15-53
FIELD	Iuka-Carmi		Ticket No.	64416
COUNTY	Pratt		HOWCO DISTRICT	Pratt
STATE	Kansas		Kind of Job	Open Hole
CONTRACTOR	Reserve Drlg. Co		Price	\$215.00
		Total Depth	4255'	
		Casing Perforations	Top - Bottom -	
		Top Packer Depth	4202'	
		Bottom Packer Depth	-	
MUD DATA		Casing or Hole Size	7 7/8"	
		Liner or Rathole Size	-	
Kind	Starch	Formation Tested	Viola	
Weight	9.95 lbs.-gal.	Size Drill Pipe	4 1/2" API FH	
Viscosity	39.5 Sec.	Size Bottom Choke	1/2"	
Filter Loss	8 c. c. Filter Cake 3/32 in.	Size Tool Valve	1"	
BT. P.R.D. No.	291 Blanked Off No	Size Hook Wall Packer	-	
		Size Rings	-	
	12 Hr. Clock No. 1550	Size D. E Wall Packer	6 3/4"	
		No. Packers	2	
Est. Gauge Depth Temp.	110 °F	PRD Device No.	1699	
		Blanked Off	Yes	
Pressure Readings	Field	Office Corrected		
Initial Hydro Mud Pressure		2254 p.s.i.		
Initial Flow Pres.		17 p.s.i.		
Tool Open	1 hour	Recovered 4000' of gas and 60' of slight gas cut mud.		
Final Flow Pres.		28 p.s.i.		
Time Closed In	20 minutes			
Closed In Pres.		100 p.s.i.		
Final Hydro Mud Pressure		2218 p.s.i.	Amount of Cushion	None
		All depths measured from	Kelly Bushing	No. Folders Reproduced
				Five

TIME

PRESSURE



Each Horizontal Line Equal to 1000 p.s.i.



HOENER

LEASE

1

WELL NO.

4

TEST NO.

H. L. MOORE

COMPANY

KANSAS

DISTRICT


LOCATION	26-26S-13W				Date	6-17-53			
FIELD	Wildcat				Ticket No.	78219T			
COUNTY	Pratt				HOWCO DISTRICT	Pratt			
STATE	Kansas		HOLE & TOOL DATA		Kind of Job	Open Hole			
CONTRACTOR	Reserve Drilg. Co.		Total Depth	4376'	Casing Perforations	Top - Bottom -			
			Top Packer Depth	4358'	Bottom Packer Depth	-			
	MUD DATA		Casing or Hole Size	7 7/8"	Liner or Rathole Size	-			
Kind	Starch		Formation Tested	Arbuckle Lime		Extra Folder Charge	-		
Weight	10.1	lbs.-gal.	Size Drill Pipe	4 1/2" API FH	Size Drill Collars	5 3/4" x 83.67'	Jars	-	
Viscosity	42	Sec.	Size Bottom Choke	3/4"	Size Surface Choke	1/2"			
Filter Loss	12.6 c. c. Filter Cake	3/32 in.	Size Tool Valve	1"	Size Pilot Valve	-			
BT. P.R.D. No.	239	Blanked Off No	Size Hook Wall Packer	-	Size Rings	-	No. Rings	-	
	12	Hr. Clock No. 2486	Size D. E. Wall Packer	6 3/4"	No. Packers	1	Total	\$215.00	
Est. Gauge Depth Temp.	110	°F	PRD Device No.	1816	Blanked Off	Yes	Witnessed By	Wendell Johns	
Pressure Readings	Field	Office Corrected	Size & Length Anchor	4 1/2" x 18'			Tester	L. A. Dugan	
Initial Hydro Mud Pressure		2285 p.s.i.	REMARKS: Opened tool with a weak blow that increased						
Initial Flow Pres.		32 p.s.i.	to strong blow and continued throughout the test.						
Tool Open	60 minutes								
Final Flow Pres.		103 p.s.i.	Recovered 1050' of gas, 270' of oil.						
Time Closed In	20 minutes								
Closed In Pres.		1426 p.s.i.							
Final Hydro Mud Pressure		2283 p.s.i.	Amount of Cushion	None		All depths measured from	Kelly Bushing	No. Folders Reproduced	Five

TIME

78219

PRESSURE

Each Horizontal Line Equal to 1000 p.s.i.



TM200 20ECLA EILW

3

