

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY DEEP ROCK & RINE DRILLING CO.

SEC. 1 T. 26 R. 14W

FARM McCandless

NO. 1

LOC. NW NW NE

330' S 300' E of N/4

COUNTY Pratt



TOTAL DEPTH 4478

COMM. 10-12-50

COMP. 11-2-50

SHOT OR TREATED

CONTRACTOR R.W.Rine Drlg Co.

ISSUED 12-2-50

10 3/4" ^{CASING} 801' cem w/500 sx.

ELEVATION 1983

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, gravel	240
shale, shells	370
red bed, shells	580
red bed, sand, shells	805
anhydrite	840
sand, shale, shells	1450
sand, salt, shells	1600
shale, shells	1875
lime	2185
lime, shale	2295
shale, sand	2435
shale	2675
shale, lime strks	2810
shale, lime	3160
lime broken	3210
lime, shale	3550
lime	3725
lime, shale	3780
lime	3892
lime, chert	3918
shale, lime	3940
lime	4034
chert, lime	4070
lime, shale	4139
lime	4215
chert	4330
lime, chert, shale	4353
Core #1	4353-4365
Core #2 (and)	4365-4375
sand	4385
shale	4410
shale, sand	4428
lime (Arbuckle)	4478
Total Depth	

Tops:

Brown Lime	3755
Lansing	3789
Conglomerate	4199
Kinderhook	4228
Viola	4293
Simpson	4355
Arbuckle	4426

Plugged: Halliburton

Plug @ 300' w/20 sx.

Halliburton Plug @ 30'

w/10 sx.