

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


Company- BISHOP OIL CO.
FarmHenderson No. 1

SEC. 2 T. 26 R. 14W
SE SE NE

Total Depth. 4380
Comm. 6-12-53 Comp. 7-1-53
Shot or Treated.
Contractor. Carl Todd Drilling Co.
Issued. 8-22-53

County Pratt

KANSAS



8 5/8 @ CASING: 880' w/ 240 sx cem.
5 1/2 @ 4375' w/ 200 sx cem.

Elevation. 1979 RB

Production. Flowed 48 BOPH

Figures indicate Bottom of Formations.

surface clay & sand	30
sand	220
shale & red bed	355
red bed & shells	685
red bed & sand streaks	730
red bed	876
anhydrite	910
shale & shells	1675
shale	1750
salt	1810
lime & shale	2945
shale	3035
lime	3190
lime & shale	3265
lime	3610
lime & shale	3760
lime	4050
lime & shale	4145
lime, shale & chert	4193
chert & shale	4210
lime, chert & shale	4253
chert	4272
chert & shale	4285
lime & shale	4298
Simpson, shale & sand	4326
lime & shale	4353
Arbuckle	4380
Total Depth	

TOPS:	
Heebner	3576
Lansing	3755
Conglomerate	4150
Mississippi	4181
Viola	4236
Simpson	4294
Arbuckle	4351

DST #1: 3887-3900, open 1 hr. rec.
40' OCM BHP 0#

DST #2: 4237-98, open 1 hr. gas to
surf. 18 min. GCM 41 min. free oil
50 min. BHP 1275#

DST #3: 4296-4326, open 1 hr. rec.
660' gas, 120' GCM sl. oil spotted,
BHP 960#

Perf 6 SPF 4236-46, flowed thru csg.
4 hrs after perf. flowed thru tbg
15 BOPH/3 hrs. then decreased to
5 BOPH. Swbd 10 BOPH/ 6 hrs. Acid.
500. Flowed 48 BOPH.

Ran Schlumberger