


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- BISHOP OIL COMPANY  
Farm- Webster No. 2

SEC. 2 T. 26 R. 14W  
NW NE SE

Total Depth. 4400  
Comm. 2-8-54 Comp. 2-26-54  
Shot or Treated.  
Contractor.  
Issued. 5-29-54

County Pratt KANSAS



Elevation. 1980 KB

CASING:  
8 5/8" 882' cem. w/240 sx  
5 1/2" 4399' cem. w/175 sx

Production. B.H.B. 2065 BO & no water

Figures indicate Bottom of Formations.

clay & gravel	235
sand rock & iron	270
shale & redbed	560
shale & shells	680
sand & shale	690
shale & shells	875
Anhydrite	900
shale & shells	1980
lime & shale	2110
broken lime	2240
lime & shale	2395
lime	2600
shale	2745
shale & lime	2915
shale	2940
lime & shale	3230
lime	3709
lime & shale	3795
lime	4077
cherty lime & shale	4120
lime & shale-Cong.	4180
lime & chert	4210
shale & chert	4253
Viola	4264
chert	4275
lime & shale	4350
shale & dolomite	4400
Total depth	

Tops:	
Heebner	3574
Brown lime	3726
Lansing	3766
Conglomerate	4148
Mississippi	4170
Viola	4222
Simpson	4293
Arbuckle	4358

Drill Stem Test #1 4224-43  
gas in 4 min., oil in 47 min.,  
open 1 hour, shut in 20 min.,  
FFP 1020, BHP 1290

Drill Stem Test #2 4243-65  
gas in 4 min., mud in 17 min.,  
oil in 30 min., open 45 minutes,  
shut in 20 minutes, IFP 1020,  
FFP 1300, BHP 1480

Drill Stem Test #3 4293-4324, gas in  
31 minutes, 45' slightly oil cut mud,  
60' heavy oil & gas cut mud, 300'  
clean oil, open 1 hour, shut in 20  
minutes, IFP 210.  
FFP 2 10, BHP 1040