

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- Anna Lacey No. 1

SEC. 5 T. 26 R.14W
SW SE NW
990' fr EL, 330' fr SL, NW/4

Total Depth. 4050 PBTB 3969
Comm. 8-20-55 Comp. 9-2-55
Shot or Treated. 3500 gal acid 3957-68
Contractor. Chas. Hulme, Drilling Contractor
Issued. 1-21-56

County Pratt

KANSAS



8 5/8 @ CASING: 940' w/ 500 sx cmt.
5 1/2 @ 4050' w/ 150 sx cmt.

Elevation. 2014 DF

Production. 82 BOPD

	Figures Indicate Bottom of Formations.
surface soil & sand	255
red clay	645
shale & shells	930
anhydrite	960
shale & shells	1820
lime	2130
lime & shale	2580
shale & shells	2700
lime & shale	2990
lime	3090
lime & shale	3210
lime	3950
gray, fine crystalline lime w/ oolicastic & oolitic porosity	3959
Gray & tan, fine crystalline lime, fair oolicastic & oolitic porosity	3971
lime	4050
Total Depth	

Plugged back to 3969

TOPS:

Anhydrite	932
Base Anhydrite	957
Wellington	1416
Base Wellington	2030
Tarkio	2968
Near Topeka	3175
Topeka	3290
Heebner	3591
Brown lime	3749
Lansing	3777

Ran Schlumberger Microlateralog Survey

DST #1: packer @ 3950, 22' anchor,
open 1 hr. good blow oil thruout, rec.
1860' gas, 75' SO&GCM, IFP 32#, FFP
63#, BHP 530#/20 min.

Producing Formation: Lansing 3957-68

Perf. 60/3979-84, 66/ 3957-68