


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. D.R. LAUCK OIL CO., INC.
Farm. Webster No. 1

SEC. 11 T. 26 R. 11W
SE NE NE

Total Depth. 4495'
Comm. 12-27-56 Comp. 1-13-57
Shot or Treated.
Contractor.
Issued. 2-23-57

County Pratt
KANSAS



CASING:
8 5/8" 267' w/225 sx cem.

Elevation. 1981' DF

Production. Dry

Figures Indicate Bottom of Formations.

clay-sand	210
red bed	380
red bed-sand	690
Anhydrite	885
shale-shells	1827
lime	2050
lime-shale	3440
lime	3565
lime-shale	3776
lime	3995
lime-shale	4055
lime	4185
lime-shale chert	4225
shale	4232
sand	4242
sand-shale	4247
shale-lime	4285
chert-lime-shale	4310
chert-shale	4360
lime-chert-shale	4380
shale-sand	4420
shale	4480
Arbuckle	4495 RTD
Total Depth	

TOPS:	Sample	Halliburton
Anhydrite	870	
Heebner	3613	3613
Douglas	3654	3655
Brown lime	3764	3764
Lansing	3792	3796
B/Kansas City	4096	4097
Mississippian	4210	4213
Kinderhook	4223	4226
Viola	4282	4284
Simpson	4382	4385
Arbuckle	4480	4483

DST # 1 - (M-D) 3932-3945 Open 30
in. weak blow 15 min; rec. 12' mud; BHP
50# in 20 min.

DST # 2 - (M-D) 4233-4242 open 45 min.
weak blow 25 min.; rec. 25' mud; BHP
60#, 30 min.

DST # 3 - (M-D) 4305-5330, open 30 min.,
weak blow 25 min., rec. 20' mud; BHP 0#
in 30 min.