

1726-15W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL CO.
Farm- Beck No. 1

SEC. 1 T. 26 R. 15W
C SE NW

Total Depth. 4588'
Comm. 5-3-62 Comp. 5-16-62
Shot or Treated.
Contractor.
Issued. 9-22-62

County Pratt
KANSAS



CASING:
8 5/8" 275' cen w/225 sx.

Elevation. 2020' KB

Production. Dry

Figures indicate Bottom of Formations.

sand & shale	600
shale & lime	975
anhydrite	1000
shale & lime	1375
shale & shell	1910
shale & lime	3840
lime	4275
lime & chert	4495
lime, chert, & sand	4586
lime, chert, & sand	4588 RTD
Total Depth	

TOPS:

Heebner	3563
Toronto	3667
Brown Lime	3804
Lansing	3828
Base Kansas City	4148
Mississippi Chert	4263
Viola	4334
Simpson Shale	4504
Arbuckle	4558

DST #1 3851-3864' op 1 hr. Rec. 65' oil
specked mud. ICIP 1260#/30 min. IF 19#
FF 28# FBHP 695#/30 min.

DST #2 4250-4275' op 1½ hr. Rec. 15' mud
ICIP 48#/30 min. IF 38# FF 38# FBHP 105#/
30 min.

DST #3 4335-4350' op 1½ hr. Rec. 10'
mud. ICIP 57#/30 min. IFP 19# FFP 19#
BHP 28#/30 min.

DST #4 4350-4385' op ½ hr. Rec. 10'
mud. ICIP 57#/30 min. IF 0# FF 0#
BHP 0#/30 min.