

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ANSCHUTZ DRILLING CO., INC.
Farm- Tatlock No. 1

.SEC. 28 T. 26 R. 15W
NE NE NW

Total Depth. 4700

Comm. 9-24-54

Comp. 10-16-54


Shot or Treated.

Contractor.

Issued. 1-1-55

County Pratt

KANSAS



Elevation. 2050 DF

Production. 455 bbls.

CASING:

8 5/8 325' w/ 250 sx cmt.
5 1/2 @ 4230' w/ 125 sx cmt.

Figures indicate Bottom of Formations.

surface clay	35
sand	165
sand & shells	290
red rock	1010
anhydrite	1045
red orck, shale & shells	1460
shale, salt & shells	1750
shale, shells & red rock	1960
shale & shells	1985
lime	2745
shale & lime	3735
lime	3849
lime & shale	3978
lime	4215
shale & lime	4260
lime	4300
lime & shale	4328
Mississippi lime	4346
sand & shale	4370
shale & lime	4415
Viola lime	4500
shale & lime	4560
Viola chert	4580
lime & shale	4625
sand & shale	4650
lime & shale	4680
lime & Arbuckle	4690
Arbuckle	4700
Total Depth	

TOPS:

Heebner	3727
Brown lime	3884
Lansing-KC	3903
Base KC	4225
Mississippian	4322
Viola	4416
Simpson	4583
Shaley Arbuckle	4657
Arbuckle	4674

DST #1: 3906-40, open 1 hr. gas to surf. 4 min. rec. 570' free oil, IFP 520#, FFP 860#, BHP 1260#

DST #2: 4324-33, open 1 hr. weak to steady blow thru-out. rec. 10' mud, BHP 425#.

DST #3: 4660-80, open 1 hr. very weak blow, rec. 130' watery mud, NSO, BHP 1660#.