

21-26-16W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- L.C. SMITHERMAN OIL PRODUCER & AURORA
 Farm- Schultz No. 1 GASOLINE CO.

SEC. 21 T. 26 R. 16W
 SE SE NW

Total Depth. 4914'
 Comm. 3-5-56 Comp. 3-30-56
 Shot or Treated.
 Contractor. L.C. Smitherman Drlg. Co.
 Issued. 4-20-57

County Edwards
 KANSAS



Elevation. 2095.4' KB

Production. 232 BOPD

CASING:

8 5/8" 373' w/360 sx cem.
 5 1/2" 4584' w/150 sx cem.

Figures Indicate Bottom of Formations.

sand-gravel	270
shale-gravel	300
shale	373
shale-red bed	645
sdv shale-red bed	880
sand-red bed	1110
shale-red bed	1600
sand-shale-red bed	1755
shale-shells-red bed	2040
shale-shells	2110
lime-Anhydrite	2290
shale-lime	2383
lime(Ft. Riley)	2464
lime-shale	2530
lime	2600
lime w/shale brks	2610
lime-shale	2705
lime-shale brks	2760
shale-lime	3659
lime w/shale strks	3729
lime w/shale brks	3771
lime s/shale	3850
lime-shale	4025
lime (K.C.)	4123
lime-shale	4151
lime (K.C.)	4338
shale-lime	4386
lime w/shale	4445
lime-shale	4498
sand-chert	4555
Mississippi chat	4560
lime-shale(Chertz)	4589
lime-chert	4622
lime-chert-sand-shale	4649
lime-chert w/shale	4670
lime-chert	4703
lime-dolomite/chert	4723
lime-chert	4751
lime chert-shale	4772
lime-shale	4820
lime-chert	4861
lime(Arbuckle)	4914 RTD
Total Depth	

TOPS: Scout

Anhydrite	2110
Heebner	3828
Brown lime	3993
Lansing	4010
B/Kansas City	4351
Cherokee shale	4462
Cherokee sand	4484
Mississippi shale	4510
Mississippi chat	4526
Kinderhook	4579
Kinderhook sand	4586
Viola	4659
Simpson	4787
Arbuckle	4862