

Till

STERL

SL

WELL LOG - - - - -

A" #7-4

Located: 1057' FSL; 1

New

USPS TRACKING #
& CUSTOMER
RECEIPT

9114 9999 4431 3687 4760 28
For Tracking or inquiries go to USPS.com
or call 1-800-222-1811.

OWNER: F. C. Hall

ROTARY DRILLING CONTRACTOR: S

COMMENCED: November 10, 1981

COMPLETED: November 23, 1981

USPS TRACKING #
& CUSTOMER
RECEIPT

9114 9999 4431 3687 4760 42
For Tracking or inquiries go to USPS.com
or call 1-800-222-1811.

TOTAL DEPTH: 4535'

LOG

CASING RECORD

0 - 434 Sand and Clay
434 - 1060 Shale
1060 - 1071 Anhydrite
1071 - 1290 Shale
1290 - 4105 Lime and Shale
4105 - 4275 Lime
4275 - 4410 Lime and Shale
4410 - 4535 Lime

Ran 10 joints 8 5/8", 23.57# OD surface casing. 419.72' set at 430' K.B. Cemented with 375 sacks 60/40 Pozmix with 3% cc. Plug down at 10:00 PM, 11-16-81, by Howco.

Ran 112 joints 4 1/2", 10.5# new casing. 4517.37' pipe set at 4526' K.B. Cemented with 100 sacks Howco Light, followed with 125 sacks 50/50 Pozmix with 18% salt, 1/8# flocele per sack and 1/8# tuffibers, 3/4 of 1% CFR-2, with 20 bbls salt flush ahead of cement. Plug down at 11:00 AM, 11-23-81, by Howco.

Deviation Surveys: 1 1/4° at 2212'
2 1/2° at 4535'

File

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - MAYHEW "A" #7-4
Located: 1657' FSL; 1655' FSL, NE/4, Section 4-26S-16W,
Edwards County, Kansas

OWNER: F. G. Holl
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 16, 1981
COMPLETED: November 23, 1981

TOTAL DEPTH: 4535'

LOG

0 - 434 Sand and Clay
434 - 1060 Shale
1060 - 1071 Anhydrite
1071 - 1290 Shale
1290 - 4105 Lime and Shale
4105 - 4275 Lime
4275 - 4410 Lime and Shale
4410 - 4535 Lime

CASING RECORD

Ran 10 joints 8 5/8", 23.57# OD surface casing. 419.72' set at 430' K.B. Cemented with 375 sacks 60/40 Pozmix with 3% cc. Plug down at 10:00 PM, 11-16-81, by Howco.

Ran 112 joints 4 1/2", 10.5# new casing. 4517.37' pipe set at 4526' K.B. Cemented with 100 sacks Howco Light, followed with 125 sacks 50/50 Pozmix with 18% salt, 1/8# flocele per sack and 1/8# tuffibers, 3/4 of 1% CFR-2, with 20 bbls salt flush ahead of cement. Plug down at 11:00 AM, 11-23-81, by Howco.

Deviation Surveys: 1 1/4° at 2212'
2 1/2° at 4535'