

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

26-26-1713

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1: 4330-4363' OP 30/60/30/60 GTS 22" 1st opening no gauge 2nd opening 10" = 36,200 20" - 20,600 30" - 17,800 Rec. 120' Sl. MO, 400' Clean gassy oil, 60' froggy oil	FP 99-176 SIP 1440-1407 BHT 112		ELECT. LOG TOPS Heebner Toronto Lansing B/KC Cher. Sh. Miss. Kind. Sh. Kind. Sd. LTD	3878 -1756 3899 -1777 4040 -1918 4336 -2214 4508 -2386 4519 -2397 4532 -2410 4550 -2428 4580
DST #2: 4504-4535' OP 45/60/45/60 Good blow both openings Rec. 100' GIP, 80' GCM	FP 57-66 SIP 706-958 BHT 114			
DST #3: 4557-4581' OP 45/75/60/90 Rec. 480' GIP, 65' O&GCM, 60' HOGCM 1st opening good blow 36"	FP 77-94 SIP 991-1089 BHT 114			
Sand, clay & Red Beds	0	447		
Red Bed & shale	447	872		
Shale	872	1866		
Shale & Red Bed	1866	2139		
Shale & Lime	2139	2969		
Lime & shale	2969	4520		
Lime	4520	4535		
Lime & shale	4535	4581		
RTD		4581		

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4	8-5/8	24#	432	Common	325 sx	2% gel 3%cc
Production		4 1/2	10.5#	4580	60-40 Poz	75 sx	10% salt, .75% CFR2, 50 sx Common w/ Latex

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	SSB	4555-58'
TUBING RECORD					
Size	Setting depth	Packer set at			
	4553'				

26-26-17W *Ind*

DRILLERS LOG

CASING RECORD:
8-5/8" set @ 432'
w/325sx cement
4 1/2" set @ 4580'
w/125sx cement
ELEVATION: 2122 KB

COMPANY: Hummon Corporation
CONTRACTOR: Big-H Drilling, Inc.
COMMENCED: December 3, 1981
COMPLETED: December 12, 1981

DESCRIPTION:
CROCKETT #7
C NE SE
Sec. 26-26S-17W
Edwards County, KS

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand, Clay & Red Beds	0	447	
Red Bed & Shale	447	872	
Shale	872	1866	
Shale & Red Bed	1866	2139	
Shale & Lime	2139	2969	
Lime & Shale	2969	4520	
Lime	4520	4535	
Lime & Shale	4535	4581	
RTD		4581	

RECEIVED
STATE CORPORATION COMMISSION
JAN - 3 1989
CONSERVATION DIVISION
Wichita, Kansas

JAN 05 1982
KANSAS GEOLOGICAL SURVEY
WICHITA BRANCH

I certify that this is a true and correct copy of the above log to the best of my knowledge.

BIG-H DRILLING, INC.

SANDRA L. MENDOZA
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. _____

Charles J. Hummer

Subscribed and sworn to before this 14th day of January, 1982 .

Sandra L. Mendoza
Notary Public