

State Geological Survey

WICHITA BRANCH

KANSAS DRILLERS LOG

15-047-20532

API No. 15 — 047 — 20,532
County Number

S. 26 T. 26S R. 17W E
Loc. 150' NW of C SE SW
County Edwards

Operator
Hummon Corporation

Address
400 One Mian Place, Wichita, Kansas


Well No. #2 Lease Name
Crockett

Footage Location
765' feet from (N) (S) line 765' feet from (E) (W) line

Principal Contractor D.R. Lauck Oil Company Geologist
Mike Mitchell

Spud Date 7/16/79 Total Depth 4430 P.B.T.D. 4370

Date Completed 7/24/79 Oil Purchaser
Clear Creek, Inc.



Locate well correctly
Elev.: Gr. 2117
DF 2120 KB 2122

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8-5/8	20#	463	Common	300 sx.	2% gel 3% cc
Production		4 $\frac{1}{2}$	10 $\frac{1}{2}$ #	4412	Halco-Lite	25 sx.	
					60-40 Pos	100 sx.	18% salt, 3/4 of 1% CFP2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2	SSB	4359-62
TUBING RECORD					
Size	Setting depth	Packer set at			
2"	4366	---			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
2500 gal. CRA acid	4359-62

INITIAL PRODUCTION

Date of first production 8/2/79	Producing method (flowing, pumping, gas lift, etc.) pumping				
RATE OF PRODUCTION PER 24 HOURS	Oil 40 bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s) 4359-62		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Hummon Corporation	DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: oil
--------------------------------	--

Well No. #2	Lease Name Crockett	
----------------	------------------------	--

S <u>26</u> T <u>26</u> S <u>R1</u> W <u>E</u> W	
---	--

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 OP45-45-45-45 Strong blow w/ gas to surface 24 min. on initial opening Rec. 30' heavy oil & gas cut mud 175' gassy mud cut oil, 370' froggy oil SIP 1243-1220 FP 76-176 BHT 132°	4335-4370			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

Date Received

Wilber Berg
Signature

Wilber Berg

Title

10/8/79

Date