

DRILLERS LOG

No. 1 Shannon

CASING RECORD:

8-5/8" @ 302'
w/250 sx cement

TOTAL DEPTH: 4563'

COMPANY: Patton Oil Company

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: 5/25/73

COMPLETED: 6/09/73

DESCRIPTION:

SW
6-26S-17W
Edwards County,
Kansas

ELEVATION: 2143 Gr

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	225	
Shale & Shells	225	303	
Shale	303	525	
Redbed	525	612	
Anhydrite	612	624	
Redbed	624	860	
Sand & Redbed	860	960	
Redbed	960	1210	
Anhydrite	1210	1224	
Redbed & Shale	1224	1420	
Shale & Shells	1420	1815	
Shale & Limestreaks	1815	2135	
Lime	2135	2140	
Lime & Shale	2140	2682	
Lime	2682	2697	
Lime & Shale	2697	2955	
Lime	2955	3060	
Lime & Shale	3060	3140	
Shale, Lime & Sand	3140	3224	
Lime & Shale	3224	3270	
Lime	3270	3410	
Lime & Shale	3410	3495	
Lime	3495	3670	
Lime & Shale	3670	3769	
Lime	3769	3854	
Shale	3854	3860	
Lime	3860	3873	
Toronto	3873	3905	
Douglas	3905	3930	
Shale & Lime	3930	4005	
Lime	4005	4465	
Lime & Shale	4465	4515	
Lime	4515	4529	
Lime & Shale	4529	4563	

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 - 1974
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.