

STANOLIND OIL & GAS CO.  
W.H. Newsom No. 1.

S1/4 Sec. 11 T. 26 R. 18 W  
SE NE SE  
1650' N SL 2310' E WL SE 1/4

Total Depth. 4845'  
Comm. 2-28-43 Comp. 4-8-43  
Shot or Treated.  
Contractor.  
Issued. 5-8-43 Rotary O-4845

*See 22-28-15*  
*all dolomite*

County. Edwards



CASING:  
8 5/8" 269'9" Com.

Elevation. 2165

Production. Dry

Figures Indicate Bottom of Formations.

cellar	8'8"	shale	4806
surface sand	70	lime	4845
sand	225	Total Depth.	
shale & shells	280		
shale	400		
sand	500		
red bed	582	Rotary Core No. 1	
lime wh	609	Rec. 5'	4807-15
red bed	900	4807-08 dense, gy dolomite	
shale red & shells	1105	4808-12 med cryst tan dolo.	
red bed & shells	1180	4812-14 fine cryst.	
anhydrite	1190	glauconitic dolomite w/ strks slight porosity	
lime & red bed	1220	4814-15 dense brown dolo.	
shale	1485	Rotary Core No. 2	
shale & shells	1655	Rec. 7'	4815-20
shale & lime	1760	4815-17 med cryst gy dolo.	
shale	1895	4817-21 med cryst gy dolo.	
shale & shells	2050	w/slight porosity	
shale & lime shells	2160	4821-23 coarse cryst gy dolomite	
lime brkn	2305	4823-25 fine cryst gy dolomite w/green pyritic shale strks	
lime	2370		
lime brkn	2490	Rotary Core No. 3	
lime	2550	Rec. 4'	4825-35
lime brkn	2605	4825-28 tan fine cryst oolitic dolomite	
lime	2815	4828-30 tan fine cryst dolomite, slight porosity	
lime brkn	2925	4830-32 tan & pink med cryst dolomite w/green sdy shale strks	
lime	2995	4832-35 tan med sugary dolomite, fair porosity	
shale	3045	Rotary Core No. 4	
lime brkn	3105	Rec. 9'	4835-45
shale & lime	3170	4835-37 gy cryst dolomite, slight vugular porosity	
shale	3230	4837-39 tan fine cryst dolomite, no porosity	
shale & lime	3275	4839-41 brown med cryst dolomite-oolitic, good porosity	
sand hd & shale	3285	4841-43 tan med cryst dolomite, slight vugular porosity.	
lime brkn	3400		
shale & lime	3475		
shale	3510		
lime	3560		
lime brkn	3875		
lime	3970		
shale	4032		
limo	4143		
lime hd	4152		
lime sft	4162		
lime hd	4173		
lime	4199		
lime sft	4227		
lime	4332		
lime sft	4337		
lime	4407		
shale	4435		
lime brkn	4470		
lime	4510	Tops: Lansing	4032
lime brkn	4541	Simpson	4714
sand hd	4545	Arbuckle	4805
sand	4611		
sand & chert	4630		
chert	4637		
lime cherty	4647		
lime	4745		
lime & shale	4772		

*Shell &*  
*A-1170*  
*LS4032*  
*V4615*  
*S477K*  
*A-4802*

*20-15*