

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

McLean #1

~~660 X 1/4 E of SE 1/4 Sec 2-26S-18W~~ SW SE NW of Section 8-26S-18W
Edwards County Kansas

Commenced: 8-10-77

Completed: 8-20-77


OPERATOR: RUPE OIL CO., INC.

Depth		Formation	Remarks
From	to		
0	225	Soil-Sand	Ran 8 jts of 28# 8 5/8" csg
225	350	Sand-Clay	set @ 345' Cemented w/
350	525	Sand-Shale	300 sks Class A 2% Gel
525	1260	Redbed	3% CC PD 5:30 a.m. 8-11-77
1260	1300	Anhy	1" to 40' w/approx 30 sks
1300	1740	Shells-Shale	Job Complete 9:30 a.m. 8-11-77
1740	2570	Shale-Lime	
2570	3170	Lime	
3170	3750	Lime-Shale	
3750	4760	Lime	
	4760 - TD		DRY & ABANDONED


STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.


JAMES S. SUTTON II

Subscribed and sworn to before me this 24th day of August, 1977.


ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.