

35- 26-19W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. SUNRAY MID-CONTINENT OIL CO.
Farm. Gus Edwards No. 1

SEC. 35 T. 26 R. 19W
C SW SW

Total Depth. 5012'
Comm. 4-4-62 Comp. 4-21-62
Shot or Treated.
Contractor. Stickle Drig. Co.
Issued. 8-17-63

County Edwards
KANSAS



CASING:

8" 329' cem w/300 sx.
5" 5004'

Elevation. 2237' DE

Production. 43 BOPD & 58 BW

Figures Indicate Bottom of Formations.

surface clay & sand	225
red bed & shells	330
red bed	1272
anhydrite	1310
shale & shells	1695
shale & sand	2165
shale	2280
lime & shale	2555
shale	2590'
lime	2705
lime & shale	2855
lime	2948
lime & shale	3240
shale	3385
shale & lime	3540
shale, chalk & lime	3659
lime	3765
lime & shale	3898
sandy lime & shale	4022
lime & shale	4120
lime	4708
lime & shale	4754
lime	4763
lime & shale	4775
chert & lime	4790
lime & chat lime	4810
chert & lime	4862
shale w/sandy lime streaks	4925
shale & lime	4944
lime & chert	4948
lime	5012
Total Depth	

TOPS: LOG

Heebner	4045
Toronto	4080
Lansing	4196
Cherokee	4712
Mississippi	4777
Kinderhook Shale	4869
Kinderhook Sand	4891
Viola	4965