

STATE OF KANSAS
STATE CORPORATION COMMISSION-CONSERVATION DIVISION
500 Insurance Building-212 North Market
Wichita 2, Kansas

DATA AND AFFIDAVIT

(File one Copy)

(On Cementing in Surface or Drive Pipe and required by Rule 82-2-123 of the Commission for compliance with Section 55-136, 55-137, and 55-138, 1947 Supplement to G. S. Kansas 1935)

Lease Owner Glen Rupe

Office Address 222 Brown Bldg., Wichita, Kansas 67202

Lease Name Michaelis Well No. 1

Well Location (Example: C N/2 NE/4 NE/4 or footage from lines)

C NE NW SEC 13 TWP 26S RGE 19W (E) County Edwards

Contractor Leben Drilling, Inc.

Office Address Box 486, Great Bend, Kansas 67530

Drilled with (cable) (Rotary) tools: Date pipe set 2-24- 19 68

SURFACE HOLE DATA

SURFACE PIPE DATA

Size of Hole 12 1/2" Csg. (New) (Used) Size 8 5/8" Wt. 20#

Depth 290' Where set on bottom

METHOD OF CEMENTING

(a) Cement: Amount and kind 250 sks. Common, 2% cc

Method: (By Service Co., Dump, Tog., etc.) Service Co.

Est. Height Cement behind pipe to surface

(b) Cementing Material: Explain method. (Example: 8-5/8 w/swag nipple run inside 15", Bridge hold 2/rock and hole filled with cementing material, 15" pipe pulled.) Cut 12 1/2" hole, ran 8 5/8"

surface casing, cement pumped down casing, displaced with water,

cement circulated to top of hole.

Describe cementing material 250 sks. Common, 2% cc

GROUND WATER INFORMATION

Depth to bottom of lowest fresh water producing stratum _____

Name of lowest fresh water producing stratum _____

Surface elevation of well _____

ADDITIONAL INFORMATION

(Additional information may be submitted on separate sheet)

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON SS,
Leslie Kite, of the Leben Drilling, Company, being
first duly sworn on oath, state: That I, have knowledge of the facts,
statements and matters herein contained and that the same are true
and correct.

Subscribed and sworn to before me on this 11th day of March 19 68
My Commission Expires:

April 1, 1971

*mailed
State Corp
3/12/68
mnc*

Leslie Kite
Alanda Nichols

SUN OILWELL CEMENTING, INC.

1314 Kansas—P.O. Box 169
Great Bend, KansasN^o 5734

TEST TICKET

Date 3-7-68 Place Kinsley 9s-1d.
 Charge to Glen Roper Order No. _____
 Mail Address _____ City _____ State _____
 Owner of Well same Contractor Leban D. Co.
 Well No. 1 Lease Michaels County Edwards Sec. 12 Twp. 26 Rng. 19
 Test No. 5 Successful No. _____ Mis-run No. _____
 Size Hole 7 3/4 Depth Well 4853 Tool Joint 4 1/2 Test Tool Size 3 1/2
 Packer Size 6 3/4 Packer set at 4334-4420 Sub Rented From same Sub Size 3 1/2 to 4 1/2
 Anchor Size 5 1/2 Length 86'
 Rat Hole Size _____ Depth to Shoulder _____ Size Bean 5 1/2
 Drill Stem: Run Dry _____ with Fluid _____
 Pressure Recorder Make Kuster AK-1 Cap. No. 3600 + 4000

RESULTS:

Time Packer Set 12:55 A.M. Hyd. Pressure 2218
 Tool Open Initial 10 Min. Tool Open Final 60 Min.
 Initial BHP 1499 in 30 Min. Final BHP 1498 in 30 Min.
 Initial Flow Pressure 153 Final Flow Pressure 1742
 Blow good Blow Through-out Test
 Recovery _____

180' of muddy salt water
1200' of salt water

no show of oil

Fluid Recovered in _____ Drill Pipe _____
 Flexweight _____ Drill Collors _____ Was Tool Plugged? no Was Anchor Plugged? no
 Mud Weight 9.7 Visc. 43 Elevation GL _____ KB 3211
 Extra Equipment _____
 Formation Tested K.C. Temperature _____

Price Job _____
 Other Charges fuel + rigging
joint
 Total Truck - 09

Approved _____

Tester _____

A ticket must be made with complete information for each run, whether successful or not.