

State Kansas County Reno

Company Messman-Rinehart Oil Company Well No. 1


Farm Nunemaker "B"

Survey _____

Block No. _____ Sec. 2 Twp. 26 S Range 9 W

Co-Ord. _____ Elev. 1685' K/B
1683' D/F

C. S/2 SW/4 SE/4 M-R Rig



50% - A. A. Seeligson, Jr., et al
25% - Chicago Group
25% - Messman-Rinehart Oil Co

3900' Miss. Chat test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 330 Ft. from S. Line _____

660 Ft. from W. Line _____ Ft. from E. Line _____

| Date | Depth | |
|---------|-------|--------------------------|
| 8-9-59 | | Location staked |
| 8-18-59 | | M.I.R.T. - Spud |
| 8-19 | | Rat-holed ahead to 350' |
| | | 8-5/8" @ 240' w/200 sx., |
| | | 4 gel., 4 c.c. |
| | | P.D. @ 8:00 a.m. 8/19/59 |
| 8-20 | 625 | Drlg. |
| 8-21 | 1725 | Drlg. (#2 @ 1535) |
| | 1235 | Anhydrite (#450) |

| Date | Depth | |
|------|-----------|------------------------------|
| | | 692294 |
| 8-22 | 2135 | Drig. (#3 @ 1935) |
| 8-24 | 3040 | On bank w/#5 |
| | 3341 | Brown Lime (-1656) |
| 8-25 | 3350 | Drig. |
| | 3371 | Lansing (-1686) |
| 8-26 | 3515 | Drig. (#6 @ 3402) |
| 8-27 | 3645 | Drig. (#7 @ 3536) |
| | | (#8 @ 3640) |
| 8-28 | 3850 | Drig. |
| | 3864 | Congl. (-2179) |
| | 3911 | Miss. (-2226) |
| 8-30 | 3935 | R.T.D. |
| | D.S.T. #1 | - 3912-35' - Op 2 hrs., GTS |
| | | in 5", Ga. 155,000 cf (too |
| | | small to measure in 20"), |
| | | Rec. 180' VSOC SW & 120' SW, |
| | | BHP 1200-670#, FP 95-145# |
| | | D. & A: 8-29-59 |