


26-26-21W
 SEC. 26 T. 26 R. 21W
 LOC. C NW SE

COMPANY KAISER-FRANCIS

FARM Bucklin NO. 1

COUNTY Ford

TOTAL DEPTH 4962'
 COMM. 9-6-67 COMP. 9-17-67
 RIGID LIN TREATED
 CONTRACTOR Leben Drilling
 ISSUED 12-2-67



CASING
 20 10
 15 8 5/8" 251' cem w/225 sx
 12 6
 13 5

ELEVATION 2276' KB
 PRODUCTION DRY/MISS OS

FIGURES INDICATE BOTTOM OF FORMATIONS

0	50 Clay, Sand, Gravel	TOPS: LOG
50	210 Shale	Heebner 4046
210	251 Red Bed	Toronto 4065
1	765 Shale	Douglas 4084
765	776 Anhydrite	Brown lime 4165
776	1340 Shale	Lansing 4175
1340	2345 Shale & Lime	Base Kansas
2345	3225 Lime	City 4579
3225	3935 Lime and Shale	Marmaton 4597
3935	4811 Lime	Cherokee 4709
4811	4880 Chalk Lime	Mississippi 4793
380	4962 Lime	Mississippi
	4962 RTD D & A	Dolomite 4846

Mississippi
 Osage 4938

8 5/8" Used Surface Casing Set @ 251' cemented with 225 sx common 2% cc Cement Circulated.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Bucklin #1, located C NW SE of Section 26, Township 26 South, Range 21 West, Ford County, Kansas as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 LESLIE KITE

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 20th day of September, 1967.