

Phillips Pet Co
#1 Guyson

Ran
Reno
21-26-94

(2' rat. bush to dar fl.)

Elev 1701

(arrived well 3400 7:15 AM 5/21/45)

8 5/8 417

Exp
Bik 54 3164

5 1/2 4161

trap 3054
Reno

Heebner (3217) 3215 d/, Dodge (3240) 3238 d/

Douglas (3258) 3258 -1555

+ M. sd (3258-67) 3256-65 por. fair stain
sharp odor (driller) probably, mostly gas - Some oil

Dn Ls (3351) 3349 d/

* LKC (3367) 3365 d/ -1664

(3369-71) 3367-79 to stain poor por

(3395-99) 3393-97 to stain " "

(3416-20) 3214-18 sl. stain poor por

trap 3430
Ran over

(mid of 5-7) (3435-50) 3433-48 d/ sheet por + stain - fair dar + test

DST (3434-50) 3432-48 5 ft casing open 30 min

(strong blow all) rec 60' about mud, little free oil top

left well 3450

9/22 AM

rich odor (odor 4 ft above mud rec.)

left well

CM (3898) 3896 d/ -2195 (Bond)

* K (3956) 3954 d/ -2253

* CV (4163) 4161 d/ -2460

14-14 → (11-11-8) circ (4164) 4164 d/ (1 hr) 2 ft dar on 11th Ls - no por
1 1/4 wh. + grey spec, 4 1/2 - no show
(1 1/2 hr) no show

(8-6) circ (4168) 4166 d/ (1 1/2 hr) 1 hr suc. del. good odor, por + sat
1 1/2 hr some along mostly came

5 1/2 cas 4161

4/4 dP 700' O/H 7 hrs with 1 BOPH

300 acc sub 5 BOPH

4/5 3500' O/H 12 hrs - acid deepened well 3 ft

TD 4169 flow head 10 1/2 BOP 40" sub 64/13 hrs

4/20 Ran tub. 500 acid pump 225 BOP 13 hrs

4/22 pump 78 BOP 1 1/2 hr & flow 130/2 hrs

1/29 1500 acid

(over)

May 1945

Samples 3000 - 4/68

$\frac{7}{4}$ phy post after acid

296 BO 70 BW

Q