

Shellys #1 (Cymman
(mercury, etc. south)

Ran
21-26-9W
NW NE SW
el 1712

(Bond) LKC 3390 - 1678

(11) 3436-40 - 1724 VSSO 0 g

(11) 3452-56 - 1740 SSO

(11) 3464-68 - 1752 SSO

MCH 3579-84 VSSO

11 3630-37 soft no show

Trip 3570 3641 3656 - broke clutch 12/23/43 3656

MCH BKC 3652 - 19 to on 3782-2070

3664-67 sl per - no stain - water

3676-81 " " " " water

3714-28 oolitic - good por - no show - water

VSSO

3732-40 nodular - poor por - sl stain

3745-47 oolitic, fair por - no show - water

VSSO

3821-23 dense, poor por - sl stain

3869-79 leached - poor por - no stain

12/26/43 6:30 PM Trip 3898

CM 3916 - 2204 wh opag & trip ch
some br sh ls - den

corel 3920 - no odor - 1 pc sl stain

corel 3930 " " - no show - no odor

12/27/43

1/6 Trip 3934 Ran W-7-R D 3945 10:30 AM

K 3968 - 2256

3965 11:46 AM

CV (4178) 2466

Trip 3973 #184021

→ 4177 df 2465

corel 4176

corel 4182 (7-7-7-4)

(2 ft) 1/2 hr fgn ls & grey speck ch

(1 ft) 1 hr sec dol, sl stain, 1 pc ls ^{good} stain

RUST (4182) 4181 df

1/9/44 loaded hole 300' water 4 PM

dr. plug CO to bottom (1 ft) 4182

7 PM - 8 PM filled 600 oil & mud & BS

Bail to 100' off bottom set 2 hr, 100' oil
additional, bail set 2 1/2 PM

1/10/44 SPM 400' oil
(over)

Dec 1943
Ran Sphs 3580-4182

Wymann # 1

400' oil in hole

1/10/44 Swab 7 PM - 12 AM (5 hrs) rec 16.44 bbls

last 2 times pulled swab no recovery

1/11/44 bailed midnight to 4:30 AM

1/2 bails oil each trip

— dr 4182-83 hidden ls (25 min) 2000-5000 ^{depth}

bailed holding bail 1 1/2 gal oil PH no water

1/12 Cored 4183-84 (15 min) hidden ls (Prestap report)

cable cores 4184-85 (13 min) brn sh ls (" " ")

cored 4185-86 (15 min) " " " (" " ")

cored 4186-87 (14 min) " " " (" " ")

cored 4187-88 (15 min) " " " (" " ") no more

1/13 finished coring 6 AM ran bail rec. 10 gal oil 8 AM

2000' oil

10:30 AM

Swab 1 PM - 2 PM, 16.7 bbls swab to 2500' from top

2 - 3 " 16.7 " " 3100 " "

3 - 4 " 20.14 " " 3600 " "

4 - 5 " 4.2 " " 3600 " "

5 - 6 " 5.04 " " 3850 " "

6 - 7 " 11.76 " " 4170 " "

7 PM - 8 AM swab 60.42 BO on 4.64 BO PH ave

swab total 134.96 BO in 19 hrs

1/14/44 swab 60.714 BO 15 hr (4.47 PH ave)

got 93 oil no wtr