

4-26-23W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, KansasCompany - SWEARER ET AL
Farm - Brown

No. 1

SEC. 4 T. 26 R. 23 W
SWc SW

Total Depth. 5755'

Comm. 4-22-46

Comp. 6-30-46


Shot or Treated.

Contractor.

Issued. 9-14-46

County. Ford

KANSAS

CASING:
13 3/8" 239'

Elevation. 2495'

Production. Dry

Figures indicate Bottom of Formations.

sand	0-30	lime	4162
surface dirt	40	shale	4177
shale & shells	85	lime	4250
sand	230	shale	4251
shale & shells	283	lime	4685
red bed & shells	410	lime & shale	4715
shale & shells	788	lime	4735
pyrite	794	shale & lime	4770
shale & shells	825	lime	4830
sand	860	lime & shale	4920
red shale & rock	980	cherty lime	4940
red rock & sand	995	lime & sand	4955
gyp	1005	lime & chert	4965
anhydrite	1027	cherty lime & shale	4985
shale & lime shells	1060	lime cherty	5020
shale red & shells	1210	lime & chert strks	5060
red rock & shale	1295	lime	5215
shale & red bed	1315	lime & shale	5240
red rock, shale & sand	1515	cherty lime	5250
red rock & shells	1578	lime	5275
anhydrite	1623	cherty lime	5305
shale & anhydrite	1740	lime & chert	5445
shale & shells	1840	lime hrd	5455
shale & salt	1920	shale & lime	5475
anhydrite, shale & salt	2015	lime	5495
shale & shells	2080	lime & shale	5510
shale & anhydrite	2215	lime	5544
shells	2215	chert & lime	5570
lime, shale & salt	2315	lime	5580
lime & shale	2355	lime & chert	5655
shale & anhydrite	2415	lime	5658
shale red & anhydrite	2455	sand	5674
anhydrite	2464	sand & lime	5718
shale blue & anhydrite	2485	lime & chert	5720
anhydrite & shale	2620	lime	5755
lime & shale	2650	Total Depth.	
lime cherty	2658	Spotted 25 sx cem. 2700-2600';	
lime med hrd	2660	filled hole w/heavy mud to	
shale lgt blue	2678	235'; spotted 25 sx cem. @ 235';	
lime sft	2687	filled hole w/heavy mud to 10';	
lime gy mod	2708	filled remainder of csg. &	
lime & shale	2720	btm of cellar w/10 sx cem.	
dolomite	2727	Tops:	
lime	2965	Dakota	490
lime & sand	2985	Cimarron	840
lime	3225	Blaine Gyp	995
lime & shale	3310	Anhydrite	1578-1628
lime brkn	3375	Hollenberg	2548
lime	3455	Ft. Riley	2721
lime & shale	3610	Hard Lime	3655
lime	3630	Topeka	3725
lime & shale	3860	Kans. City	4251
lime brkn	3925	Mississippi	4964
lime	4010	Simpson	5658
porous lime	4080		