

TRILOBITE
TESTING, INC.

DRILL STEM TEST REPORT

Prepared For: **Vincent Oil Corp.**

155 N Market Ste. 700
Wichita Ks. 67202

ATTN: Jim Hall

11/26/24 Ford KS

Fischer 1-11

Start Date: 2010.07.08 @ 16:15:00

End Date: 2010.07.08 @ 23:09:39

Job Ticket #: 39327 DST #: 1

ORIGINAL

Trilobite Testing, Inc
PO Box 1733 Hays, KS 67601
ph: 785-625-4778 fax: 785-625-5620



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

Vincent Oil Corp.

155 N Market Ste. 700
Wichita Ks. 67202

ATTN: Jim Hall

Fischer 1-11

11/26/24 Ford KS

Job Ticket: 39327

DST#: 1

Test Start: 2010.07.08 @ 16:15:00

GENERAL INFORMATION:

Formation: **Morrow**

Deviated: No Whipstock: ft (KB)

Time Tool Opened: 18:16:20

Time Test Ended: 23:09:39

Test Type: Conventional Bottom Hole

Tester: Harley Davidson

Unit No: 33

Interval: **4833.00 ft (KB) To 4928.00 ft (KB) (TVD)**

Total Depth: 4928.00 ft (KB) (TVD)

Hole Diameter: 7.78 inches Hole Condition: Fair

Reference Elevations: 2502.00 ft (KB)

2491.00 ft (CF)

KB to GR/CF: 11.00 ft

Serial #: 8674

Inside

Press@RunDepth: 1368.83 psig @ 4836.00 ft (KB)

Start Date: 2010.07.08

End Date:

2010.07.08

Start Time: 16:15:05

End Time:

23:09:40

Capacity: 8000.00 psig

Last Calib.: 2010.07.08

Time On Btm: 2010.07.08 @ 18:15:30

Time Off Btm: 2010.07.08 @ 20:04:10


TEST COMMENT: IF- Strong blow BOB 30 sec.

IS- No blow back.

FF- Strong blow BOB 30 sec.

FS- No blow back.

PRESSURE SUMMARY



Time (Min.)	Pressure (psig)	Temp (deg F)	Annotation
0	2398.39	112.27	Initial Hydro-static
1	669.87	112.87	Open To Flow (1)
15	1111.15	126.31	Shut-In(1)
46	1464.60	123.49	End Shut-In(1)
46	1145.97	123.26	Open To Flow (2)
60	1368.83	125.75	Shut-In(2)
109	1467.29	123.11	End Shut-In(2)
109	2254.63	123.21	Final Hydro-static

Recovery

Length (ft)	Description	Volume (bbl)
3450.00	100% water trace of mud.	48.39

Gas Rates

Choke (inches)	Pressure (psig)	Gas Rate (Mcf/d)
----------------	-----------------	------------------



TRILOBITE
TESTING, INC

DRILL STEM TEST REPORT

TOOL DIAGRAM

Vincent Oil Corp.

Fischer 1-11

155 N Market Ste. 700
Wichita Ks. 67202

11/26/24 Ford KS

Job Ticket: 39327

DST#: 1

ATTN: Jim Hall

Test Start: 2010.07.08 @ 16:15:00

Tool Information

Drill Pipe:	Length: 4821.00 ft	Diameter: 3.80 inches	Volume: 67.63 bbl	Tool Weight:	2000.00 lb
Heavy Wt. Pipe:	Length: 0.00 ft	Diameter: 0.00 inches	Volume: 0.00 bbl	Weight set on Packer:	25000.00 lb
Drill Collar:	Length: 0.00 ft	Diameter: 2.25 inches	Volume: 0.00 bbl	Weight to Pull Loose:	75000.00 lb
		Total Volume:	67.63 bbl	Tool Chased	0.00 ft
Drill Pipe Above KB:	15.00 ft			String Weight: Initial	58000.00 lb
Depth to Top Packer:	4833.00 ft			Final	75000.00 lb
Depth to Bottom Packer:	ft				
Interval between Packers:	95.00 ft				
Tool Length:	122.00 ft				
Number of Packers:	2	Diameter:	6.75 inches		
Tool Comments:					

Tool Description

Tool Description	Length (ft)	Serial No.	Position	Depth (ft)	Accum. Lengths
Change Over Sub	1.00			4807.00	
Shut In Tool	5.00			4812.00	
Hydraulic tool	5.00			4817.00	
Jars	5.00			4822.00	
Safety Joint	2.00			4824.00	
Packer	5.00			4829.00	27.00 Bottom Of Top Packer
Packer	4.00			4833.00	
Stubb	1.00			4834.00	
Perforations	2.00			4836.00	
Recorder	0.00	8355	Inside	4836.00	
Recorder	0.00	8674	Inside	4836.00	
Change Over Sub	1.00			4837.00	
Drill Pipe	62.00			4899.00	
Change Over Sub	1.00			4900.00	
Perforations	25.00			4925.00	
Bullnose	3.00			4928.00	95.00 Bottom Packers & Anchor
Total Tool Length:	122.00				



**TRILOBITE
TESTING, INC**

DRILL STEM TEST REPORT

FLUID SUMMARY

Vincent Oil Corp.

Fischer 1-11

155 N Market Ste. 700
Wichita Ks. 67202

11/26/24 Ford KS

Job Ticket: 39327

DST#: 1

ATTN: Jim Hall

Test Start: 2010.07.08 @ 16:15:00

Mud and Cushion Information

Mud Type: Gel Chem

Cushion Type:

Oil API:

deg API

Mud Weight: 9.00 lb/gal

Cushion Length:

ft

Water Salinity:

25000 ppm

Viscosity: 51.00 sec/qt

Cushion Volume:

bbl

Water Loss: 9.58 in³

Gas Cushion Type:

Resistivity: ohm.m

Gas Cushion Pressure:

psig

Salinity: 6300.00 ppm

Filter Cake: inches

Recovery Information

Recovery Table

Length ft	Description	Volume bbl
3450.00	100% water trace of mud.	48.394

Total Length: 3450.00 ft Total Volume: 48.394 bbl

Num Fluid Samples: 0

Num Gas Bombs: 0

Serial #:

Laboratory Name:

Laboratory Location:

Recovery Comments: RW .25 @ 85F = 25000 chlorides

Pressure vs. Time

