


34-26-26W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- DEEP ROCK & PROSPECT PARTNERS
Farm- H. A. Kinkaid No. 1
Total Depth. 5465
Comm. 6-21-52 Comp. 7-19-52
Shot or Treated.
Contractor. R. W. Rine Drilling Co.
Issued. 10-25-52

SEC. 34 T. 26 R. 26W
NW NE SE
2304' N of SL, 992' W of EL, N
SE $\frac{1}{4}$
County Ford
KANSAS



CASING:
13 3/8" 278' cem w/325 sx

Elevation. 2567 D.F.
2570 (red)

Production. dry

Figures indicate Bottom of Formations.

CORING RECORD: No cores
were taken.

Zero Point - Rotary Bushing.

surface sand, shale 230
sand, shale 285
sand, shale, shells 550
sand, shale 900
red bed 995
anhydrite 1045
shale, shells 2290
shale 2470
shale, lime 2545
shale, shells 2625
shale, sand 2650
lime 2713
lime, shale 2828
lime 2840
shale, lime 2915
lime 3085
shale, lime 3170
lime 3220
lime, shale 3320
lime 3400
lime, shale 3610
lime 3678
lime, shale 3746
lime 4220
lime, shale 4275
lime 4343
lime, shale 4385
lime 4724
lime, shale 4760
lime 4868
lime, sand 4900
lime 5115
lime sandy 5142
lime, chert 5168
lime 5465
Total Depth RTD

Tops:
Topeka 3840
Heebner 4152

Lansing-Kansas City 4256
Marmaton 4696
Mississippian
St. Genevieve 4986
St. Louis 5067
Spargen 5231
Warsaw 5420

DRILL STEM TESTS:

- #1 5006-5062 Tool open 1
hr, rec. 25' rotary mud,
BHP 975#.
#2 5236-5281 Tool open one
hr rec. 1380' muddy salt
water. BHP 1575#. FP 685#.
#3 5420-5465 Tool open 1 hr.
Rec. 285' muddy salt water.
BHP 1500#.