

State Kansas County Pratt

Company Messman-Rinehart Oil Co. Well No. 10

Farm Berg "A"

Survey 3050 0418

Block No. 27 Twp. 26 S Range 14 W

Co-Ord. Elev. 1985' K/B

S/2 SE/4 NW/4

M-R Rig

1983' D/F

1981' Gr

50% - A. A. Seeligson, Jr.

25% - Chicago Group

25% - Messman-Rinehart Oil

FO - Texas Co. (ORI)

DHM- Lario (\$2,500.)

To be comm. on or before

5/1/63

4650' Arbuckle test

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
4/5/63		M.I.R.T. - Spud
4/6		10-3/4" @ 275' w/275 sx. cem.
		6 gel. 6 c.c., P.D. @ 11:45 a.m. 4/6/63
4/8	1975	On bank w/#2 bit
4/9	2380	Drlg. (Lm. & Shale) #3 @2281'
4/10	2665	Drlg. (#4 @ 2550)
4/11	2955	Drlg. (#5 @ 2955)
4/12	3250	Drlg. (Lm. & Shale)

Date	Depth	694542
4/13	3244	Topeka (-1259) (22' higher than D.H. to West)
	3300	Drlg.
	3490	Drlg. (#6 @ 3293)
	3687	Heebner (-1702)
	3846	Brown Lime (-1861) #7 @ 3550
	3875	Lansing (-1890) #8 @ 3872
		(22' higher than DH to west)
		(50 unit kick, fair show oil
		in samples)
DST #1	- 3880-90'	- Op 1 hr., GTS in 5",
		Ga. 458,000 - 10"
		416,000 - 20"
		396,000 - 30"
		362,000 - (stabilized)
		Rec. 65' oilcut mud, 60' very
		hvy oil-cut mud; 70' mdy oil,
		50' wtr., BHP 1424-1351#,
		FP 115-126#
4/16	DST #2	- 3907-4020 - Op 1 hr., Rec. 120' mdy
		wtr., BHP (30") 1392-1247#,
		FP 42-73#
	3928	Drlg.
DST #3	- 4011-24'	- Op 1 hr., GTS in 32", Rec.
		20' MCO, 120' hvy O&GCM, 60'
		wtr., BHP 1440-1225#, FP
		105-130#

(estimate 5' of thinning from top of Lansing)

State Kansas County Pratt

Company Messman-Rinehart Oil Co. Well No. 1


Farm Berg "A"

Survey _____

Block No. _____ Sec. 27 Twp. 26 S Range 14 W

Co-Ord. _____ Elev. 1985' K//b

S/2 SE/4 NW/4



Page 2

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line

Ft. from S. Line

Ft. from W. Line

Ft. from E. Line

Date	Depth	
4/18/63	DST #4 - 4024-47'	- Op 1 hr., Rec. 10' mud w/few specks of oil,, SI 30'
	SIP 1204-63#, FP 31-31#	
	4086	Drlg.
4/19	4230	Drlg.
4/20	4304	Conglomerate (-2319)
	4312	Miss. (-2327)
DST #5 -	4302-27'	- Op 1 hr., GTS in 10''(tstm)
		Rec. 40' GCM, BHP 1466-1298#, FP 42-31#

694542

Date	Depth	
4/22	4359	Viola (-2374), no sho, no por (79' & 68' higher than other well)
	4475	Drlg. (#18 bit)
	4465	Simpson Shale (-2480) no sho
	4475	Simpson Sand (-2490) no sho
4/23	4537	Drlg.
4/24	4557	Arbuckle (-2472)
	4590	R.T.D. (Ran Log)
		Dry and Abandoned
		4/24/63

Log Tops:

3688		Heebner
3838		Br Lm.
3862		Lansing
4300		Conglomerate
4313		Miss.
4348		Viola
4466		Sp. Sh
4474		Sp. Sd.
4560		Arbuckle