

CONFIDENTIAL

WELL COMPLETION REPORT AND
DRILLER'S LOGKANSAS Geological Survey
WICHITA BRANCHAPI No. 15 — 069 — 20,137
County Number

Operator

DONALD C. SLAWSON

Address

200 Douglas Building Wichita, Kansas 67202

Well No.

1

Lease Name

Rowan 'I'

Footage Location

330

feet from (N) (S) line

330

feet from (E) (W) line

Principal Contractor

Slawson Drilling Co. Inc.

Geologist

George Mueller

Spud Date

July 24, 1981

Date Completed

Aug. 4, 1981

Total Depth

5120'

P.B.T.D.

NA


Directional Deviation

Oil and/or Gas Purchaser

NA

Loc. NE NE NE

County Gray

640 Acres
N

Locate well correctly

Elev.: Gr. 2701

DF 2705 KB 2708

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 1/4"	8 5/8"	24#	409'	60/40 poz	350 sx	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

RELEASED

AUG 1 1983

FROM CONFIDENTIAL

INITIAL PRODUCTION

Date of first production

Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION
PER 24 HOURS

Oil

bbis.

Gas

MCF

Water

Gas-oil ratio

bbis.

CFPB

Disposition of gas (vented, used on lease or sold)

Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name ROWAN 'I'	Dry Hole
S <u>9</u> T <u>26</u> R <u>29</u> W <u>E</u> W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 46 Sand 46 - 417 Sand and shale 417 - 1603 Shale 1603 - 1636 Sand and shale 1636 - 1837 Shale and lime 1837 - 3564 Shale 3564 - 5120 Shale and lime 5120 RTD DST #1 4870-4914 (ST LOU Zn) 30-60-30-30, WkB/30", Rec. 10' Mud, NS IFP 44-44#, ISIP 397#, FFP 44-44#, FSIP 59#			LOG TOPS B/ANHY 1814 (+894) HEEB 4083 (-1375) TORO 4098 (-1390) LANS 4140 (-1432) STK 4463 (-1755) HUSH 4569 (-1861) U/CHER 4725 (-2018) L/CHER 4758 (-2050) ST. GEN 4856 (-2148) ST. LOU 4888 (-2180) LTD 5118 (-2410)	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>William R. Horigan</i> WILLIAM R. HORIGAN, Operations Engineer Title September 1, 1981 Date
---------------	---

9-26-29W

WELL LOG *State Geological Survey*
WICHITA BRANCH

OPERATOR: **DONALD C. SLAWSON**
200 DOUGLAS BUILDING
WICHITA, KANSAS 67202

LEASE: #1 Rowan 'I'
NE NE NE Sec. 9-26-29W
Gray County, Kansas

CONTRACTOR: **SLAWSON DRILLING COMPANY, INC.**
200 DOUGLAS BUILDING
WICHITA, KANSAS 67202

COMMENCED: July 24, 1981

COMPLETED: August 4, 1981

CASING: Surface - 8 5/8" @ 409' w/350 sx 60/40 poz

0 -	46	Sand
46 -	417	Sand and shale
417 -	1603	Shale
1603 -	1636	Sand and shale
1636 -	1837	Shale and lime
1837 -	3564	Shale
3564 -	5120	Shale and lime
5120		RTD

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

I, William R. Horigan, OF THE **SLAWSON DRILLING COMPANY, INC.**
UPON OATH STATE THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE
LOG OF THE #1 Rowan 'I' TEST.

William R. Horigan

William R. Horigan, Operations Engineer