

State Geological Survey
WICHITA BRANCH

CONFIDENTIAL

OCT 23 1981

KANSAS DRILLERS LOG

API No. 15 — 069 — 20,037
County Number

Operator
DONALD C. SLAWSON

Address
200 Douglas Building Wichita, Kansas 67202

Well No. 1 Lease Name Todd 'B'

Footage Location
1980' feet from XXX (S) line 660' feet from XX (W) line


Principal Contractor Slawson Drilling Company, Inc. Geologist Ralph Ruwwe

Spud Date March 2, 1979 Total Depth 5130' P.B.T.D. N/A

Date Completed March 14, 1979 Oil Purchaser N/A

S. 10 T.26 R.29W E W
Loc. C NW SW
County Gray

640 Acres
N



Date: APR 30 1982
FROM CONFIDENTIAL
Locate well correctly

Elev.: Gr. 2722
DF 2724 KB 2727

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	23#	411'	60/40 poz	300 sx	2% gel; 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil	Gas	Water	Gas-oil ratio
		bbls.	MCF	bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Todd 'B'	Dry Hole	
S 10 T 26 R 29W E W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
0 - 262 Shale and sand 262 - 750 Shale 750 - 1675 Shale and sand 1675 - 1808 Shale and shells 1808 - 1832 Anhydrite 1832 - 2051 Shale 2051 - 4195 Lime and shale 4195 - 4452 Lime 4452 - 4527 Lime and shale 4527 - 4531 Lime 4531 - 4712 Lime and shale 4712 - 4870 Lime 4870 - 4920 Lime and shale 4920 - 4942 Lime 4942 - 5015 Lime and shale 5015 - 5130 Lime 5130 RTD			<u>LOG TOPS</u> B/ANH 1820 (+907) KRI 2662 (+75) HEEB 4082 (-1355) LANS 4137 (-1410) STK 4489 (-1762) PAW 4684 (-1957) U/CHER 4726 (-1999) L/CHER 4756 (-2029) ST.GEN 4848 (-2121) ST.LOUIS 4908 (-2181) SPERG 5086 (-2359) LTD 5130 (-2403)
DST #1 4677-4710 (PAWN) 30-30-30-30, V-WkB/died 20", Rec. 10' M, NS. IFP 32-32#, ISIP 1386#, FFP 32-32#, FSIP 1322#, 125°. Drlg @ 4870' DST #2 4895-4920 (ST. LOUIS) 30-60-30-75, V-WkB. Rec. 10' Mud, NS. IFP 35-35#, ISIP 1233#, FFP 35-35#, FSIP 1160#, 135°.			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature R.J. THATCHER Engineer Title April 22, 1979 Date		

10-26-29W
CONFIDENTIAL

WELL LOG

OCT 23 1981

DL

OPERATOR: Donald C. Slawson
200 Douglas Building
Wichita, Kansa 67202

LEASE: #1 Todd 'B'
C NW SW of Sec. 10-26-29W
Gray County, Kansas

CONTRACTOR: Slawson Drilling Co., Inc.
200 Douglas Building
Wichita, Kansas

COMMENCED: March 2, 1979

COMPLETED: March 14, 1979

CASING: Surface - 8 5/8" @ 411' w/300 sx 60/40 poz

State Geological Survey
WICHITA BRANCH

0 - 262 Shale and sand
262 - 750 Shale
750 - 1675 Shale and sand
1675 - 1808 Shale and shells
1808 - 1832 Anhydrite
1832 - 2051 Shale
2051 - 4195 Lime and shale
4195 - 4452 Lime
4452 - 4527 Lime and shale
4527 - 4531 Lime
4531 - 4712 Lime and shale
4712 - 4870 Lime
4870 - 4920 Lime and shale
4920 - 4942 Lime
4942 - 5015 Lime and shale
5015 - 5130 Lime
5130 RTD

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS.

I, R.J. THATCHER, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Todd 'B' test.


R.J. THATCHER

Subscribed and sworn to before me this 22nd day of April, 1979.

in sh.