

20-26-29W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Mardock, Wichita, Kansas

Company- PHILLIPS PETROLEUM & N.C.R.A.
Farm- Jury "A" No. 1

SEC. 20 T. 26 R. 29W
C SW SE

Total Depth. 6095'
Comm. 1-25-60 Comp. 2-10-60
Shot or Treated.
Contractor. J. M. Johnson Drig.
Issued. 3-25-61

County Gray KANSAS



Elevation. 2764' RB

CASING:
13 3/8" 200' cem.
9 5/8" 2200' cem.

Production. Dry

Figures Indicate Bottom of Formations.

sand, red beds	200	Warsaw	5474
sand	350	Osage	5570
clay	741	Gilbert City	5770
gyp, sand	1288	Kinderhook Sand	5848
gyp, shale	1402	Viola	5863
sand, gyp, pyrite	1463	Simpson	6004
gyp, Anhydrite	2210	Arbuckle	6034
sand, shale, anhydrite	2500		
shale, sand anhydrite	2532		
lime, shale	2838		
lime, shale, cherty strks	3086		
lime, shale	3837		
chalky lime	3997		
lime, shale	4171		
lime, shale, chert	4969		
shale, sandy lime (Miss. lime)	5134		
lime, chert	5471		
dolomite	5535		
lime, chert	6046		
Arbuckle lime	6095		
Total Depth			

TOPS: SCOUT

Base Florence	2982
Wreford	2998
Council Grove	3028
Neva	3184
Foraker	3253
Admire	3260
Wabaunsee Group	3408
Tarkio	3507
Elmont	3561
Howard	3743
Topeka	3796
Heebner	4121
Toronto	4131
Lansing	4214
Base Kansas City	4600
Marmaton	4611
St. Genevieve	4927

4927
2760
2123