

State Geological Survey

WICHITA BRANCH

KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.API No. 15 — 069 — 20,026
County NumberOperator
Gear Petroleum CompanyAddress
1325 Vickers KSB&T Building Wichita, Kansas 67202Well No. #1 Lease Name
Hamlin

Footage Location

2310 feet from (N) (S) line 330 feet from (E) (W) line


Principal Contractor
Slawson Drilling Company Geologist
Benny SingletonSpud Date
4-15-78 Total Depth P.B.T.D.
5120' N/ADate Completed
4-24-78 Oil Purchaser
N/A

15-069-2 0026

s. 22 t. 26 r. 29 E
W

Loc. SW SW NW

County Gray



Locate well correctly

Elev.: Gr. 2732'

DF 2735' KB 2737'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 ¹ / ₄ "	8 5/8"	28#	415'	60/40 Pozmix	300	2% Gel, 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			

TUBING RECORD

N/A N/A N/A

Size	Setting depth	Packer set at
N/A	N/A	N/A

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used			Depth interval treated
N/A			N/A

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)				
N/A		N/A				
RATE OF PRODUCTION PER 24 HOURS	Oil N/A	Gas bbls.	N/A	MCF	Water N/A	Gas-oil ratio bbls.

Disposition of gas (vented, used on lease or sold)				Producing interval(s)		
N/A				N/A		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Gear Petroleum Co.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.	Lease Name	
1	Hamlin	Dry Hole
S 22 T 26S R 29 E W		

WELL LOG


Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
Heebner	4127	-1390		
Lansing	4223	-1486		
Cherokee	4786	-2049		
St. Genevive	4933	-2196		
St. Louis	4990	-2223		
LTD	5122	-2385		
RTD	5120	-2383		
DST #1, 4922-63', 30-30-30-30", weak blow/1" & died, Rec 5'			M, FP 20-20#, SIP 29-29#.	
DST #2, 4986-5000', 30-30-30-30", weak blow/15" & died, Rec 15'			O&GCM, IFP 20-20#, F	
RAN ELECTRIC LOGS.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received


 R. James Gear

Signature

Owner

Title

May 12, 1978

Date