

WICHITA BRANCH
KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-069-20025

API No. 15 — 069 — 20,025
County Number

Operator

Gear Petroleum Company

Address

1325 Vickers KSB&T Building Wichita, Kansas 67202

Well No.

#1

Lease Name

R & O Cattle Company

Footage Location

330 feet from (N) S line 330 feet from (E) W line

Principal Contractor

Slawson Drilling Company

Geologist

Benny Singleton

Spud Date

4-25-78

Total Depth

5150'

P.B.T.D.

N/A

Date Completed

5-4-78


Oil Purchaser

N/A

S. 22 T. 26 R. 29 E

Loc. SW SW SW

County Gray

640 Acres
N

Locate well correctly

Elev.: Gr. 2744'

DF 2747' KB 2749'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	416'	60/40 Pozmix	325	2% Gel, 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
N/A	N/A	N/A			
TUBING RECORD					
Size	Setting depth	Packer set at			
N/A	N/A	N/A			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
N/A	N/A

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
N/A	N/A				
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	CFPB
	N/A bbls.	N/A bbls.	N/A bbls.	N/A	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		
N/A			N/A		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Gear Petroleum Co.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name R&O Cattle Co.	Dry Hole
S 22 T 26S R 29 E W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
LOG TOPS				
Heebner	4142	-1393		
Lansing	4238	-1489		
Cherokee	4799	-2050		
St. Genevieve	4948	-2199		
St. Louis	5006	-2257		
LTD	5150	-2401		
RTD	5150	-2401		
RAN ELECTRIC LOGS.				
DST #1 4954-5006', 30-30-30-30", Rec 5' M, IFP 32-32#, FFP 32-32#, SIP 288-160#.				
DST #2 5005-27', 30-30-30-30", Rec 20' OSM, IFP 15-15#, FFP 15-15#, SIP 148-89#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 R. James Gear	
	Signature	
	Owner	
	Title May 12, 1978 Date	