

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

35-26-33W


Company. STANOLIND OIL & GAS COMPANY
Farm. Kisner G.U. "B" **No.** 1

SEC. 35 **T.** 26 **R.** 33W
 SW SW NE
 150' N. of SL 150' E. of WL
 NE/4
County Finney

Total Depth. 2760
Comm. 1-31-53
Shot or Treated.
Contractor.
Issued. 4-18-53

Comp. 3-11-53

KANSAS



CASING:

8 5/8" 867' cem. w/450 sx
 5 1/2" 2740' cem. w/900 sx

Elevation. 2921
 2925 (and)

Production. 9,601,000 Gas

Figures indicate Bottom of Formations.

clay, sand	411
sand, clay, shale	745
clay blue, shale	835
red bed	1200
gyp, shale	1670
gyp	1720
gyp, anhy.	2010
anhy. shale	2418
anhy. shale, lime	2450
lime	2760
Total Depth	

Tops:
 Herington Krider 2628
 Winfield 2687
 Towanda 2740

Ran 1 1/4" tubing set at 2716'
 Schlumberger ran Gamma Ray
 & Micro Log.

McCullough Tool Co. perforated
 w/6 shots per ft. as follows:
 Herington Krider 2628-441',
 2646-48', 2651-53', 2661-63',
 2667-69'.

Winfield 2687-94', 2698-2704',
 2712-14', 2719-22', 2727-29'.

Dowell Inc. acidized as follows:

Towanda	4000 gals. 15%
Herington Krider	2500 gals. 15%
Winfield	2000 gals. 15%
All Zones	18000 gals. 7 1/2%