

33-26-33W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

FARM Atkins "J"

NO. 1

SEC. 33 T. 26 R. 33W

LOC. NE NE SW
100' S. & 100' W.
of Center

COUNTY Finney

TOTAL DEPTH 2770'

COMM. 10-26-49


COMP. 11-1-49

SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 6-2-51

KANSAS



CASING

8 5/8" 760' cem w/325 sxs.
5 1/2" 2769' cem w/700 sxs.

ELEVATION 2929

PRODUCTION 9,240,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay & sand	60
sand	190
sand, shale & shells	480
sand	500
shale & shells	580
sand & shale	675
shale & shells	745
shale	760
red bed	850
shale & shells	960
shale, shells & streaks anhydrite	1600
shale & shells	1840
anhydrite & shale	1940
shale & shells	2280
anhydrite & shale	2580
shale & lime	2755
anhydrite & lime	2770
Total depth	

Tops:

Herington	2564
Upper Krider	2596
Lower Krider	2622
Winfield	2658
Upper Ft. Riley	2714

Perforated:

70 shots	2600-14
80 shots	2622-38
110 shots	2658-80
40 shots	2714-22

SIP 412.5