

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.


FARM Atkins "K" NO. 1

SEC. 34 T. 26 R. 33W

LOC. NE NE SW
100' S. & 100' W.
of Center

COUNTY Finney

KANSAS



TOTAL DEPTH 2770'

COMM. 11-2-49

COMP. 11-8-49

SHOT OR TREATED

CONTRACTOR Corbett & Barbour Drlg. Co.

ISSUED 6-2-51

CASING

8 5/8" 760' cem w/325 sxs.
5 1/2" 2769' cem w/700 sxs.

ELEVATION 2927

PRODUCTION 11,700,000 gas

FIGURES INDICATE BOTTOM OF FORMATIONS

clay & sand	230
shale & shells	660
sand, shale & shells	700
shale & shells	840
red bed & shale	1530
shale	1755
shale & shells	1855
anhydrite & shells	1950
shale & shells	2235
shale	2260
anhydrite & shale	2380
anhydrite & shells	2443
shale, anhydrite & lime	2550
anhydrite & shale	2640
shale & lime	2770
Total depth	

Tops:

Herington	2580
Upper Krider	2608
Lower Krider	2628
Winfield	2670
Upper Ft. Riley	2720

Perforated:

70 shots	2612-26
80 shots	2634-50
100 shots	2670-90
40 shots	2722-30

SIP 411.7