

32-26-33W

OPERATOR: MOBIL OIL CORPORATION
FIELD: KS HUGOTON COUNTY: FINNEY
WELL: ATKINS 3 SECTION: 32-26S-33W
API NO. 1505520911

DATE	REMARKS
----	-----
90 JUL ¹⁰ 09	SPUD WELL; DRLG TOH FOR PLUG BIT, TIH DRLG
90 JUL 10	CIRC SURVEY, TOH RU CSG CREW RUN CSG CIRC PRIOR TO CMTG CEMENTING CSG WOC
90 JUL 11	CUT OFF, WELD ON HEAD, NU & TST BOP DRLG PLUG & CMT DRLG NEW FM 942 TFB DRLG FR/1930-2450'
90 JUL 12	DRLG TO 2950 C&C HOLE TRIPPING TO RUN LOGS RU LOGGERS LOGGING
90 JUL 13	RUN CSG CIRC PRIOR TO CMTG CMT CSG SET SLIPS, CUT OFF, ND BOP, RELEASE RIG
90 JUL 14	RD LOGGERS TIH C&C HOLE TO RUN CSG LD DP & DC

DEC

MOBIL OIL CORPORATION

DRILLING COMPLETION SUMMARY

WELL: ATKINS 3
API: 1505520911
WELL TYPE: DEVELOPMENT

MATCH NUMBER: 901020

COORDINATES: 3971' FSL 1429' FEL
SECTION: 32-26S-33W
COUNTY: FINNEY
WELL SPUDDED: 90 JUL 10
REACHED TD: 90 JUL 11
RIG RELEASE: 90 JUL 13

FIELD: KS HUGOTON
STATE: KS

GROUND ELEVATION: 2937
KB ELEVATION: 0
OBJECTIVE: CHASE
PROD. CASING DEPTH: 0

ADDITIONAL COMMENTS

D1

11/30/90

DEC 1 1990

OPERATOR: MOBIL OIL CORPORATION
FIELD: KS HUGOTON COUNTY: FINNEY
WELL: ATKINS 3 SECTION: 32-26S-33W
API NO. 1505520911

DATE

90 JUL 11 CASING_OD 8-5/8" TOP_CSG 0 SHOE_DEPTH 941
CMT CMT W/318 SXS CL 'H LITE' W/65-35-6 (65% CMT) W/3% CACL2,
CMT YIELD 1.89, WTR 10.9, SLURRY WT 12.7; TAILED IN W/153 SXS
CMT CL 'H' W/3% CACL2, YIELD 1.08, WTR 4.3, SLURRY WT 16.4;
CMT PREFLUSH W/20 BW, FULL CIRC, PIPE RECIP, FLOATS HELD.
CMT
CMT

90 JUL 13 CASING_OD 5-1/2" TOP_CSG 0 SHOE_DEPTH 2950
CMT CMT CSG W/210 SXS 'H LITE' W/65/35/6 (65% CMT), YIELD 1.84,
CMT WTR 9.9, SLURRY WT 12.7, TAIL IN W/180 SXS CL 'H' W/50-50-
CMT LITE POZ + 2% GEL, 2% CACL2, YIELD 1.26, WTR 5.75, SLURRY
CMT WT 14.2; PREFLUSH W/20 BW, FULL CIRC, PIPE RECIP, FLOATS
CMT HELD.
CMT

RECEIVED
STATE OF KANSAS
DEPT. OF REVENUE

DEC 2 1990

RECEIVED
STATE OF KANSAS
DEPT. OF REVENUE