

20-26-34W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- MAGNOLIA PETROLEUM CO.
Farm- C. L. Reeve No. 2

SEC. 20 T. 26 R. 34W
C SW NE

Total Depth. 5180'
Comm. 1-18-59 Comp. 2-18-59
Shot or Treated.
Contractor. General Drilling
Issued. 7-11-59

County Finney
KANSAS



CASING:
8 5/8" 816' cem w/600 sx.
5 1/2" 5178' cem w/975 sx.

Elevation. 2965'

Production. 289 BOPD

Figures indicate Bottom of Formations.

surface hole	565
sand & shale	770
red bed	1226
shale	1883
shale & lime	3462
lime, shale & chalk	3700
lime & shale	4227
lime, shale & chalk	4390
lime	4987
lime & shale	5122
Mississippi lime	5180
Total Depth	

TOPS:	
Winfield	2570
Topeka	3643
Lansing-Kansas City	3896
Marmaton	4470
Cherokee	4619
Atoka	4826
Morrow	4888
St. Genevieve	4988
St. Louis	5030

PERFORATIONS

#1 Perf. 5103-10 w/28 sh. Swabbed hole down to 5143. Swabbed 90 BNO in 5 hrs. NW Last hr. 23 BOPH Treated w/1000 gals, reg. acid. MP 200#, min. 0 Used 122 BLW Swab 122 BLW & 24 BAW in 4 hrs. All load recovered. Swab 329 BNO NW in 12 hrs. 400' off bottom. Last 4 hrs. 27 BPH Gr. 31.4 @ 60.

#2 Perf. 5035-70', w/140 sh. Tested dry two hrs. Acidized w/2000 gals. reg. 15% acid, MP 500#, final 200#, Rate 3.8 BPM Vac. in 2 min. Used 120 bbls. load Swab 120 BLO & 48 BAW in 5 hrs. All load recovered.