

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

20-26-34W


Company- MAGNOLIA PETROLEUM CO.
Farm- E. Brown No. 2

Pleasant Prairie 16

SEC. 20 T. 26 R. 34W
C NE SW
C NE SW

County Finney
KANSAS

Total Depth. 5210'
Comm. 11-24-58 Comp. 1-20-59
Shot or Treated.
Contractor. General Drilg. Co.
Issued. 3-7-59



Elevation. 3007'

Production. 244 BOPD, NW

CASING:
8 5/8" 1820' cem w/600 sx.
5 1/2" 5208' cem w/475 sx.

Figures Indicate Bottom of Formations.

sand & shale	270
shells	736
shale, sand & redbed	1049
redbed & gyp	1285
redbed, sand & shale	1612
lime, shale & redbed	2386
shale & lime	2837
lime, shale & chalk	3148
lime, ashy chalk	3517
shale & lime w/chalky strks	3949
lime & chalk	4257
lime & shale	5085
Core #1 5068 to 5125 - Full Recovery	
Core #2 5126-to 5183 - Full Recovery	
Core #3 5184 to 5210 - Full Recovery	
Total Depth	

TOPS:	
Winfield	2622
Heebner	3911
Lansing-Kansas City	3956
Marmaton	4528
Cherokee	4674
Atoka	4878
Morrow	4939
St. Geneieve	5014
St. Louis	5074

PERFORATIONS:
Perf. 5133-45 w/48 sh. tested dry 2 hrs.
Treated w/1000 gals. reg. acid thru 5 1/2"
csg. MP 700#, min. 300# final 400#.
Rate 5 GPM Swab 50 BLW in 1 1/2 hrs.