


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

10-26-34W

Company - WHITE EAGLE OIL CO.
Farm - Government No. 2

10
SEC. 7 T. 26 R. 34W
SE SE NW
330' N of S1 and 2310' E
of W1/4 of NW/4

County. Finney
KANSAS



Retary tools 0 to 2540
Cable tools 2540 to 2706.
Total Depth. 2706'
Comm. 3-28-48 Comp. 4-13-48
Shot or Treated. Acidized w/13000 gals 15% and 4,000 of 7 1/2%
Contractor.
Issued. 10-9-48

CASING:

10 3/4" 528' Cem w/400 Sx.
7" 2526' Cem w/750 Sx.

Elevation. 2963.2nd.

Production. 12,530,000 72.hrs
Gas.

Figures Indicate Bottom of Formations.

sand and gravel	500
clay	655
redbed, shale & shells	1015
red bed	1190
anhydrite	1220
shale and sand	1325
red rock & shale	1605
redbed, shale & salt	1855
salt and shale	1885
lime	1940
shale and lime	2020
lime & anhydrite	2120
lime anhydrite & shale	2310
lime and shale	2410
lime	2540
lime	2568
shale, brkn	2570
lime	2578
shale	2583
lime	2615
shale	2618
shale and lime	2640
lime	2690
shale	2693
lime	2706
total depth	

Tops:

Hollenberg	2491 to 2502
Herrington	2538 to 2546
Krider	2550 to 2570
Winfield	2586 to 2611
Upper Ft. Riley	2643 to 2680
Lower Ft. Riley	2693 to 2706

Liner Record:

198' 4" , 5 1/2" 14# Top 2507' 8"
Bottom 2706'

Acidized w/13000 gals 15% and
4,000 gals of 7 1/2%.