

WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


18-26-34W

Company. WHITE EAGLE OIL CO.
Farm. Reeves No. 1

SEC. 18 T. 26 R. 34W
SE SE NW
330' NS1 & 2310' EWL of NW $\frac{1}{4}$

County. Finney

KANSAS



Total Depth. 2700'

Comm. 2-11-48

Comp. 3-21-48

Shot or Treated. Acidized W/13,000 gals. 15% & 4,000 gals. 7 $\frac{1}{2}$ %.

Contractor.

Issued. 7-31-48

Rotary Tools 0' to 2518'

Cable Tools 2518' to 2700'

CASING:

10-3/4" 560' Cem. W/350 Sx.

7" 2504' Cem. W/750 Sx.

Elevation. 2980' *Ind.*

Production. 14,013,000 Gas

Figures Indicate Bottom of Formations.

sand	100
sand, gravel & clay	455
sand & clay	555
shale	566
shale gy	810
redbed	915
red bed & shale	1295
red bed & shalls	1860
snhydrite & red bed	1875
snhydrite & shale	1940
sand & r d bed	2055
red bed & shells	2190
lime & shale	2534
lime	2545
shale & lime	2551
shale	2556
lime	2571
lime hard	2587
lime	2591
red rock	2595
brkn lime & shale	2612
lime brkn	2622
lime sty	2653
brkn lime sft	2667
lime medium	2700
Total Depth	

Tops:

Wellington	2200-2508
Hollenberg	2430-2450
Herrington	2508-2516
Krider	2518-2538
Winfield	2554-2579
Upper Ft. Riley	2612-2646
Lower Ft. Filey	2662-2695