

Fr11-279


C11-237

MAP NO. FIRST REPORT & COMPLETION OWWO ELEV. 3001 ODF
 STATE Kans COUNTY Finney SEC. 7 TWP. 26S RGE. 34W
 OPERATOR Champlin Oil & Refining LOC. C SW SE
 WELL NO. 1 FARM NAME Earl Campbell FT. FROM _____ LINE _____
Pleasant Prairie FT. FROM _____ LINE _____
 FR. 11/24/61 SPUD _____ COMP. 11/24/61

CONT./GEOL.

COMPLETION RECORD

NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a <u>Morr</u>	<u>4910-46</u>	<u>76</u>	<u>500A & Frac</u>
b _____	_____	_____	_____
c _____	_____	_____	_____
d <u>Cal P</u>	_____	_____	_____



a I. P. OIL/DIST. 185 WTR. No GAS _____ M.C.F.P.D. _____ CHK. _____ HRS. 24
 b " " " " " "
 c " " " " " "
 d _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____
 GOR. _____ GR. 35.6 deg PSTD 4956 TD 5200

SIZE	DEPTH	CASING - CEMENT RECORD W/SAX.	SIZE	DEPTH	W/SAX.
<u>10"</u>	<u>829</u>	<u>550</u>	_____	_____	_____
<u>5 1/2"</u>	<u>5200</u>	<u>300</u>	_____	_____	_____

OPERATOR Champlin Oil & Refining WELL NO. #1 Earl Campbell ELEV. 3001 ODF

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
OWWO	OLD INFORMATION		(ODF elev tops & datum)		
			LKC	3890	- 889
OTD	5200		BKC	4442	-1441
			Marm	4457	-1456
Was completed as oil well			Chero	4600	-1599
2/25/59 frm St L perfs			Atoka	4816	-1815
5128-40.			Morr sh	4879	-1878
			Morr sd	4940-48	-1939
NEW INFORMATION:			St Gen	4966	-1965
MICT est 9/1/61. PB 5115			St L	5050	-2049
40/5092-5102, 28/5058-65,			LTD	5200	-2199
St L, 500A- Chann, \$ dry - NS.					
Sqz 5058-5102, PB 5044, 32/5020-28 & 16/4996-5000 & 32/					
4983-91 & 24/4968-74 (St Gen) \$ dry, 500A \$ dry, NS					
PB 4956, 28/4910-17 & 24/4928-34 & 24/4940-46 (Morr)					
\$ dry, 500A, \$ 3 1/2 BOPH, NW, Frac (20,000# sd X 20,000 oil)					
\$ 1d. POP. State Pot: 11/3/61 (8 hr pump) Cal P					
185 BOPD/NW, Gr 35.6 deg. Morr 4910-46.					

COMPLETED