

A-10-207

2989GL

MAP NO. K-79

ELEV. 3000KB, 2998DF

STATE Kansas COUNTY Finney SEC. 33 Twp 26S Rge 34W

OPERATOR Helmerich & Payne, Inc. 150' N of Loc. C SW SE


WELL NO. 38 FARM NAME Jones "C" FT. FROM _____ LINE _____

COL Pleasant Prairie (PD 5200) FT. FROM _____ LINE _____

FR. 9-11-61 SPUD 9-7-61 COMP. 10-13-61

CONT./GEOL. Company Tools

NAME PRODUCING INTERVAL	COMPLETION RECORD		PERF. W/HOLES	TREATMENT RECORD
	FROM - TO			
<u>Mississippian</u>	<u>5082-5164</u>		<u>30</u>	<u>1000 Ac.</u>
b				
c				
d				



d I. P. OIL/DIST. P/149 BOPD 0.9% GAS M.C.F.P.D. _____ CHK. P HRS. 24

b " " " " " " " " " "

c " " " " " " " " " "

d _____

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. 35° PBTD 5190 TD 5612-5216

SIZE	DEPTH	CASING - W/SAX.	CEMENT RECORD SIZE	DEPTH	W/SAX.
<u>8 5/8"</u>	<u>778</u>	<u>350</u>			
<u>5 1/2"</u>	<u>5214</u>	<u>200</u>			

OPERATOR Helmerich & Payne, Inc. WELL NO. #38 Jones "C" ELEV. 3000 KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
Heebner	3941		Topeka	3501	
Toronto	3954		Heebner	3939	
Kansas City	3982		Toronto	3952	
Marmaton	4571		Lansing	3981	
			Base Kansas City	4547	
			Marmaton	4573	
			Cherokee	4711	
			Atoka	4916	
			Morrow	4975	
			Ste Genevieve	5042	
			St. Louis	5081	

Spud 9-7-61. 8 5/8" @ 778 w/350 sx.
 Core #1 (Mississippian) 5090-5126½, Rc 36½' lm & sh.
 Core #2 (Mississippian) 5126½-5140, Rc 13½' dnse lm.
 Core #3 5140-86, Rc 46' lm & sh.
 RTD 5216. Logs. 5½" @ 5214 w/200 sx.
 P/18/5155-64, Swb 1d/NS, 1000-Ac, Swb 1d & Swb 30 BNOPH/3 hrs. FL 4200'.
 P/12/5082-88. Set BP @ 5110. Swb 83 BO/5 hrs. Pld BP @ 5110.

CO 5190.

POP. Pmp 164 BO/24 hrs.

IP pump 149 BO + 0.9% wtr-PD, Gty 35°, from Mississippian
5082-5164. 10/13/61.

LIBERAL LOG TOPS

3000 KB

Winfield 2642 (+358)

Heebner 3942 (-942)

Toronto 3952 (-952)

Lansing 3980 (-980)

Marmaton 4572 (-1572)

Morrow 4976 (-1976)

Ste. Gen 5040 (-2040)

St. Louis "A" 5080 (-2080) pmp 149 BO + 0.9% wtr

"B" 5154 (-2154) 10' por; \$ 30 BOPH

"C" 5183 (-2183) 13' por

TD 5216