


MAP NO. 2-163W K-78 2974EGr ELEV. 2982DF 2984KB
 STATE Kans COUNTY Finney SEC. 33 TWP. 26S RGE. 34W

OPERATOR Helmerich & Payne, Inc 150' N of C. C SW SW
 WELL NO. 39 FARM NAME Jones "0" 810 FT. FROM S LINE
Pleasant Prairie 660 FT. FROM E LINE

FR. 12/26/61 SPUD 12/20/61 COMP. 2/20/62

CONT./GEOL. Graham-Micharlis Drlg Tools

COMPLETION RECORD			
NAME PRODUCING INTERVAL	FROM - TO	PERF. W/HOLES	TREATMENT RECORD
a <u>St Lou</u>	<u>5078-5146</u>	<u>36</u>	<u>6000A & Frac</u>
b			
c			
d <u>P</u>			



a I. P. OIL/DIST. 112BO WTR. 9BW GAS M.C.F.P.D. CHK. HRS. 24
 b " " " " " "
 c " " " " " "
 d

D & A ()

SIP# _____ FI TP # _____ FI CP# _____ SIBHP _____

GOR. _____ GR. _____ PBTB 5160 (Est) TD 5204

CASING - CEMENT RECORD	
SIZE	DEPTH
<u>8 5/8"</u>	<u>741</u>
<u>5 1/2"</u>	<u>5202</u>

OPERATOR Helmerich & Payne WELL NO. 39 Jones "0" ELEV. 2984KB

SAMPLE TOPS	DEPTH	SUB SEA	ELEC. TOPS	DEPTH	SUB SEA
KB tops & datum					
Hb	3902	- 918	Top	3472	- 488
Tor	3914	- 930	Hb	3900	- 916
Lans	3943	- 959	Tor	3920	- 936
RTD (St Lou)	5204	-2220	Lans	3944	- 960
			BKC	4506	-1522
RTD 5204. 5 1/2" @ 5202 w/125 sx.			Marm	4528	-1544
RUCT & CO Est 5160 PBTB. 20/			Chero	4673	-1689
5136-46 (Miss) No sho nat,			Atoka	4875	-1891
1000A, (15%) § 1d, § 5 BOPH/			Morr	4937	-1953
NW, Frac ; (10,000 GO x 10000#			St Gen	5005	-2021
sd) Rec 1d, § 5 BOPH/NW/NT,			St Lou	5071	-2087
PB 5120, 16/5078-86 (Miss)			LTD	NA	
No sho nat, 5000 Jell A, Did					
not rec 1d, CO 5160 (est PBTB) POP. P 112 BO + 9 BW/24 hrs,					
Gr 33 deg, St Lou 5078-5146.					

CORRECTION (1/31/62) Was App N/2 SE SE, Is 150' N of C SW SW
 Was SC, Is Pleasant Prairie Pool.

COMPLETED

LIBERAL ELECTRIC LOG TOPS

2984 KB

Heebner 3902 (-918)

Toronto 3912 (-928)

Lansing 3982 (-998)

Marmaton 4226 (-1542)

Morrow 4938 (-1954)

Ste. Gen 5004 (-2020)

St. Louis 5070 (-2086) IP 112 BO + 9 BW/24 hrs

RTD 5204