


State Kansas Field Pl. Prairie
 Company Helmerich & Payne County Finney
 Farm USA "E" No. 3
 Sec. 17 Twp. 26S Range 34W

Spot corr. 100' N of C SW SE
~~C SW NW~~
 Contractor Co. Tools St. Lo 5100'

Remarks



Comm. 2/13/60 Comp. 3/30/60
 Elev. 145 DF 2971 GL KB 2974 TD 5168 PB 5133
 Pay St. L. 5107-15

I.P. P. 107.76 BOPD Press.
 Casing Record: 13 3/8 7" 773/400
 20" 10 3/4 5 1/2"
 16" 8 5/8 2 1/8 5165/675

LOCATION

	Log	Datum
FEB 10 FEB 17	Top 3418	
FEB 24 <u>sp csg 42660</u>	Hb 3836	
<u>Hb 3843 Tor 3858</u>	Tor 3849	
MAR 2 <u>Lan 3894 44603</u>	Lan 3886	
<u>RTD 5168 log.</u>	B/KL 4438	
<u>DST (SP) 5000-18</u>	Mn 4459	
<u>q/m. max 130' oil</u>	Chop 4610	
<u>+ 420' max oil</u>	Atk 4812	
<u>151P 695/30</u>	Mpr 4873	-1902
<u>FP 84-189</u>	St. G 4939	-1968
<u>FSIP 695/30</u>	St. L. 5027	-2056
<u>ca WOCT</u>	Cg 5107	
MAR 9 <u>MCT</u>	<u>15</u>	
MAR 16 <u>CO 5133 P16/5107-</u>		
<u>15 N.S. A/1000</u>		
<u>sub 54 BO mouth / 6 hrs.</u>		
<u>sub 73 BO " " / 10 hrs</u>		
<u>WO PU</u>		
MAR 23 <u>P 53 BO mouth / 12 hrs</u>		
<u>WOT</u>		
MAR 30 <u>IP P 107.76 BOPD</u>		
<u>mouth qv 32.8 @ 539</u>		
<u>St. L. 5107-15</u>		

LIBERAL TOPS

2974 KB

Winfield 2552 (+422)

Heebner 3836 (-862)

Toronto 3849 (-875)

Lansing 3886 (-912)

Marmaton 4458 (-1484)

Morrow 4872 (-1898) T 66', no sand

St. Gen 4938 (-1964)

St. Louis "A" 5026 (-2052)

"B" 5107 (-2133) 8' por, C 107 BOPD

"C" 5142 (-2168) 6' por

TD 5168