


**

State Ks. Field N.W. PLEASANT PRAIRIE
 Company McKnabb & Lindsey County FINNEY
 Farm Kahn - Devlin No. 3-19
 Sec. 19 Twp. 26 S Range 34 W

Spot NE SW SE

Contractor

Remarks P.D. 5200



Comm. 3-31-58 Comp. 6-18-58

Elev. DF 3004 GL 2998 KB TD 5169 PB

Pay 5110-25 mins

pump I.P. 144 ROPD Press.

Casing Record: 13 3/8 7"

20" 10 3/4 5 1/2" 5168/ ccm.

16" 8 5/8 823/450

	Sample	Log
apud, cog		
φ 3600	TOP	3457 HB 3882
APR 1 6 φ 4765	HB	3884 TORO 3896
APR 2 3E 4963-5005	LAN	3930 LAN-928 3932
Rec 43'-4' ls scal	MARM	4500 MARM 4502
oil str		4 TORO 4866
6' ls scal oil str		MOR-1925 4929
shly, no pow		(card)
20' shly sh.		Misc-2007 5011
4' fig sh shly ss N.S.		ST L-2052 5056
9' sh		
€ 5055-81 Rec 26'		
1/2' oil ls oil str		
10 1/2' ls dec chly N.S.		
4' " oil gd oil sh		
sh pow		
7' ls shly oil, focus		
4' " dec		
€ 5081-5120 Rec 39'-26' ls dec oil N.S.		
13' ls shly oil gd pow oil sh		
RTB 5169 log, cog, WOCT		
APR 3 0 MAY 7 MAY 1 4 MAY 2 1		
MAY 2 7 MIST		
no further info. available		

JUN 4

MIST

P/60 5110-25, fill up w/1800'
oil -45", Surf 20 BNOBH-6'

JUN 11

1st, 15g, ~~prop~~ POP

JUN 18

84 BNO + no wth -14'
← 1st calc 144 BOPD
allow. 37 BOPD

LIBERAL TOPS

3007

Winfield 2589 (+418)

Heebner 3884 (-877)

Toronto 3896 (-889)

Lansing 3932 (-925) T 82', no ss

Marmaton 4500 (-1493)

Morrow 4928 (-1921) T 82', no ss

St. Gen 5010 (-2003)

St. Louis "A" 5054 (-2047) 5' por, C 4', Sat. 5066-

"B" 5110 (-2103) 14' por, C pump 144 BOPD

"C" 5152 (-2145) 4' por

TD 5169