

8' sh ~~grn~~
 E 5065-5103 Now pulling - show oil
 JUN 18 Pac 38' - 5' sh grn, 8' sl grn soft
 3' ls ~~the cli foss fi - case xln~~
 5' ls foss per oil str
 4' " ~~doe fi - med xln N.S.~~
 1' " ~~lff and N.S.~~
 3' " ~~oil cli per oil str~~
 8' " ~~fi xln ool sli per + oil str~~
 1' " ~~doe ool fi xln~~

E 5129-54 Pac 24 1/2' - 8 1/2' ls doe
 fi xln ool sli cty
 3' ls ool oil str
 7' " AA N.S.; 6' ls doe fi xln N.S.
 RTO 5194 log, cog, uoctr

JUN 25 MCT, CO. 5170
 P/40 5137-47, Snd 1 BOPH - north
 fine 10 (ca 50%) x 10 sd
 Snd 45-50 BOPH - no wtr

JUL 2 ~~15g~~ JUL 9 prep POP
 E pump 175 BOPD - north - 24'
 allow. 37 BOPD

LIBERAL TOPS

2988 Corr L-5
 2978 KB

- Winfield 2564 (+424)
- Heebner 3850 (-872)
- Toronto 3870 (-882)
- Lansing 3898 (-970) XW
- Marmaton 4470 (-1482)
- Morrow 4900 (-1972) T 210', no sand
- St. Gen 5010 (-2132) St Gen. 5010 -2022
- St. Louis 5076 (-2098) St L 5 076 -2088
- "B" Zone 5136 (-2158) pump 175 BOPD 5136 -2148
- C Zone 5174 - 2186

The Lansing at 3942 (-964) appears to be the
 correlative pick in Eubank Area