


State Ks. Field PLEASANT PRAIRIES
 Company Mc KNABB & LINDSEY County FINNEY
 Farm RUHN - DEVLIN No. 6-19
 Sec. 19 Twp. 26 S Range 34 W

Spot CNR NE SE

Contractor

Remarks P.D. 5200' Miss



Comm. 7-18-58 Comp 8-20-58
 Elev. L+S DF 2987 GL 2992 KB 2990 TD 5175 PB 5150
 Pay 511-24 St Louis

Pump I.P. 185 BOPD Press. (count)
 Casing Record: 13 3/8" 7"
 20" 10 3/4" 5 1/2" 5174/650
 16" 8 5/8" 830/450

Loc.	Sample	Log
JUL 23 spud , CSG φ 2810	TOP 3456 HB	3875
	HB 3879	Toro 3889
JUL 30 φ 4314	TORO 3895	LAN 3934
AUG 6 4978-99	LAN 3928	MARM 448
Rec. 21'	MARM 4491	Atoka 4842
4' ss w/ calc + shly	Atoka 4849	Mor-1708 4905
12' sh	Mor 4909	(mass) 1973
5' ls w/ shly scat	ST GEN 4994	ST GEN 499
sho oil (96-99)	ST L. 5037	ST Louis 503
€ 4999-5020 Rec. 21'		-2036
11' ls AA. scat. S.O. fr. (4999-5010)		
10' ls shly N.S.		
€ 5041-87 Rec. 46'		
all ls gray buff		
all shly, chly		
(46-48), sh. S.O. - B zone		
AUG 18 € 5088-5118		
Rec. 29 1/2 - 1 1/2 sh		
26' ls drw		
2' " w/ S.O.		
€ 5118-38 Rec. 21'		

12' 1s ~~ool~~ bldg oil
9 " ~~dee~~ U.S.

613552

RTD 5175 - log, ~~no 5'~~
AUG 20 ~~egg~~, MICT, C.B. 5150
P/52 5111-24, Sand 10 BOPH - 1'
wtr, Ac 1000, Sand 35 BOPH (no wtr)
gas tsln POP
← pump 185 BOPD (no wtr)
allow: 67 "

LIBERAL TOPS

2999 KB

Winfield 2592 (+401)

Heebner 3878 (~~-885~~) (-879)

Toronto 3890 (~~-897~~) (-891)

Lansing 3924 (~~-925~~) or 3968 (-978)

Marmaton 4488 (~~-1495~~) (-1489)

Morrow 4904 (-1905) T 86', no sand

St. Gen 4990 (~~-1997~~) (-1991)

"B" Zone 5110 (-2117) 12/12, pump 185 BOPD (no wtr)

"C" Zone 5156 (~~-2163~~) (-2157)

TD 5175

→ St. Lo "A" 5030 (-2031)

Frank