

FORMATION

TOPS

28

Sec.

26

Twp.

35W

Rge.

NW NW SE

Location

Kearny

County

Kansas

State

3081

Elevation

Magnolia Pet.

Company

1

Well No.

Wampler-USA

Farm

CSO Tops

Her. 2584

U.K. 2610

L.K. 2626

Winf. 2672

U.F.R. 2733

L.F.R. 2774

Feet from _____ Line

Feet from


Feet from _____ Line

Feet from

CASING

10 3/4" 833 (450)

7" 2844 (1000)



Producing Formation _____

T. D.

2845

I. P.

22.000M

Date

Sp. 9-22-48.

R.T.D. 2845. RUST C.O. Perf. 144 holes 2774-2801.

A/7000 gals., 1.460M. Set plug @ 2757. Perf. 96

holes 2734-52. A/1000 gals., 890MCF. A/6000 gals.,

1.530M. Set plug @ 2699. Perf. 96 holes 2671-94.

A/1000 gals., 1.930M. A/6000 gals., 3.060M. Set

plug @ 2659. Perf. 72 holes 2640-54. A/7000 gals.,

2.790M. Set plug @ 2635. Perf. 120 holes 2610-33.

A/1000 gals., 870MCF. A/6000 gals., 1.430M. Drove

all plugs to T.D., B.D. 4.830M. I.P. 22.000M

R.P. 407#

NOV 2 '48